STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

VAOT Metric

SUMMARY OF ESTIMATED QUANTITIES

FULL E & C	EROSION CONTROL			BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
				1		1	EA	REMOVAL OF STRUCTURE (300 SM - EST.)	529.15	
				10		10	EA	BEARING DEVICE ASSEMBLY (POT)	531.10	
								***** BEGIN OPTION ITEMS *****		
					11	11	m	450mm PCCSP 2.01(68mm x 12mm)	601.0416	
					11	11	m	450mm CAAP 1.91(68mm x 12mm)	601.0216	
					11	11	m	450mm CPEP	601.0915	
								***** END OPTION ITEMS *****		
					3	3	EA	CAST IRON GRATE WITH FRAME, TYPE D	604.47	
					5	5	HR	BULLDOZER RENTAL, TYPE I	608.10	EST
					10	10	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST
					10	10	HR	TRUCK RENTAL	608.37	EST
					5	5	HR	LOADER RENTAL, TYPE I	608.40	EST
					3600	3600	HR	TRUCK-MOUNTED ATTENUATOR	608.45	EST
					40	40	m^3	DUST CONTROL WITH WATER	609.10	EST
					1	1	t	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15	EST
	75					75	m^3	STONE FILL TYPE I	613.10	
	12					12	m^3	STONE FILL TYPE II	613.11	
					7	7	t	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	
					10	10	EA	BOUNDARY MARKERS	619.10	EST
					1	1	EA	STEEL MARKER POSTS	619.16	
					2	2	EA	REMOVING AND RESETTING PROPERTY MARKERS	619.20	EST
	160					160	m	CHAIN LINK FENCE, 1.2m (MOD.)	620.11	
					330	330	m	SNOW FENCE (MOD. - PDF)	620.70	
					46	46	m	STEEL BEAM GUARD RAIL	621.20	
					1	1	EA	MANUFACTURED TERMINAL SECTION (TANGENT)	621.505	
					3	3	EA	ENERGY ABSORPTION ATTENUATOR	621.56	
					1	1	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	
				38		38	m	ALUMINUM APPROACH RAILING (MOD.-ANODIZED BLACK)	621.74	
					70	70	m	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	0.1
					140	140	m	TEMPORARY TRAFFIC BARRIER	621.90	3

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATE OF VERMONT
AGENCY OF TRANSPORTATION

Town Of HARTLAND	Bridge No. 60
Highway No. U.S. ROUTE 5	Log Sta. Surv. Sta.
U.S. ROUTE 5 OVER LULLS BROOK	

SUMMARY OF QUANTITIES

Designed By S.E. COSILMON	Drawn By R. REMY / G.F. O'NEIL
Checked By Date J. R. McDUFFEE 2/04	Bridge Design Supervisor J. MIECZKOWSKI Date 2/04
PROJECT HARTLAND	PROJECT NO. BRS No. 0113(22)
I.G.C. Info. M:\14562O1VAOT Hartland\zf204frm.dgn	
Bridge Sheet No.	Sheet 4 of 86

12-AUG-2004