



TEMPORARY DETOUR
NOT TO SCALE

*PAYMENT FOR ALL ITEMS WITHIN DETOUR TYPICAL TO BE PAID UNDER ITEM 528.10, EXCEPT BITUMINOUS CONCRETE PAVEMENT

TEMPORARY PARKING AREA
(TO BE PAID UNDER ITEM 528.10)
NOT TO SCALE

TEMPORARY SIDEWALK
(TO BE PAID UNDER ITEM 528.10)
NOT TO SCALE

LEGEND

- — TRAFFIC SIGNAL POLE WITH LUMINAIRE
- ⊗ — REFLECTORIZED PLASTIC DRUMS (SEE STD. E-106M) DRUM SPACING (IN FEET) IS EQUAL TO DETOUR SPEED (IN MPH)
- — TYPE III BARRICADES SEE STD. E-107AM
- PAVEMENT MARKING REMOVAL
- ⊙ — SIGNAL HEAD AND PHASE

TEMPORARY DRIVEWAY TABLE

| DRIVEWAY LOCATION | RADIUS | WIDTH | REMARKS |
|---------------------|----------|-------|---------|
| DETOUR STA 5+059 LT | 6m, 3.6m | 4m | PAVED |

- NOTES:**
- ALL TRAFFIC RELATED SIGNS SHALL BE REMOVED OR COVERED WHEN SIGNAL IS NOT OPERATING.
 - ITEM LOCATIONS ARE APPROXIMATE.
 - THE CONTRACTOR SHALL BE RESPONSIBLE TO CONFIRM ANY MEASUREMENTS IN THE FIELD.
 - PAYMENT FOR THE TEMPORARY PARKING AREA, SIDEWALK, BLOCK WALL, AND GUARDRAIL SHALL BE INCLUDED UNDER ITEM 582.10 AND SHALL INCLUDE COSTS FOR REMOVAL.
 - FOR ADVANCE WARNING SIGNS LAYOUT, SEE SHEET 22
 - ALL WORK ZONE SIGNS SHALL BE ASTM TYPE VII, VIII OR IX.

STATE OF VERMONT AGENCY OF TRANSPORTATION

| | | | |
|--|---------------------|--------------------------|----------------------|
| Town Of | HARTLAND | Bridge No. | 60 |
| Highway No. | U.S. ROUTE 5 | Log Sta. | |
| | | Surv. Sta. | |
| U.S. ROUTE 5 OVER LULLS BROOK | | | |
| TRAFFIC CONTROL PLAN | | | |
| Designed By | S.E. COSILMON | Drawn By | R.REMY / G.F. O'NEIL |
| Checked By | Date | Bridge Design Supervisor | |
| | J. R. McDUFFEE 2/04 | J. MIECZKOWSKI Date 2/04 | |
| PROJECT | HARTLAND | PROJECT No. | BRS No. 0113(22) |
| I.G.C. Info. M:\1456201 VAOT Hartland\z7204bdr.dgn | | | |
| Bridge Sheet No. | | Sheet | 20 of 86 |