STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

VAOT Metric

SUMMARY OF ESTIMATED QUANTITIES

NON-GOVT. PARTICIPATING	UTILITY	E & C ITEMS	TRAINING	EROSION CONTROL	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
						150	150	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
						550	550	HR	FLAGGERS	630.15	EST
		1					1	LS	FIELD OFFICE–ENGINEERS	631.10	–
		1					1	LS	TESTING EQUIPMENT – CONCRETE	631.16	–
		1					1	LS	TESTING EQUIPMENT – BITUMINOUS (MOD)	631.17	–
		1					1	LU	FIELD OFFICE – TELEPHONE (NOT A BID ITEM)	631.25	–
			1600				1600	HR	EMPLOYEE TRAINEESHIP	634.10	
						1	1	LS	MOBILIZATION	635.10	–
						1	1	LS	TRAFFIC CONTROL	641.10	
						960	960	M	DURABLE 100 mm WHITE LINE	646.40	27
						940	940	M	DURABLE 100 mm YELLOW LINE	646.41	18
						25	25	M	DURABLE 600 mm STOP BAR	646.46	2
						21	21	EA	DURABLE LETTER OR SYMBOL	646.50	
						2800	2800	M	TEMPORARY 100 mm WHITE LINE	646.60	1
						2900	2900	M	TEMPORARY 100 mm YELLOW LINE	646.61	62
						25	25	M	TEMPORARY 600 mm STOP BAR	646.66	2
						21	21	EA	TEMPORARY LETTERS OR SYMBOLS	646.70	
						40	40	EA	LINE STRIPING TARGETS	646.76	EST
					1140	840	1980	SM	GEOTEXTILE UNDER STONE FILL	649.31	6.3
				1400			1400	SM	GEOTEXTILE FOR SILT FENCE	649.51	EST
				130			130	SM	GEOTEXTILE FOR FILTER CURTAIN	649.61	EST
				120			120	KG	SEED	651.15	EST
				10			10	KG	SEED–WINTER RYE	651.17	EST
				895			895	KG	FERTILIZER	651.18	EST
				8			8	T	AGRICULTURAL LIMESTONE	651.20	EST
				9			9	T	HAY MULCH	651.25	EST
				100			100	EA	HAY BALES FOR EROSION CONTROL	651.26	EST
						175	175	CM	TOPSOIL	651.35	18
					565		565	SM	GRUBBING MATERIAL	651.40	
				1			1	LS	EROSION PREVENTION & SEDIMENT CONTROL PLAN	652.10	
				1025			1025	HR	MONITORING EROSION PREVENTION	652.20	
									& SEDIMENT CONTROL PLAN		
				1			1	LU	MAINTENANCE OF EROSION PREVENTION	652.30	
									& SEDIMENT CONTROL PLAN (NOT A BID ITEM)		
				4700			4700	SM	EROSION MATTING	654.10	EST
						26	26	SM	TRAFFIC SIGNS, TYPE A	675.20	0.78
									***** BEGIN OPTION ITEMS *****		
						124	124	M	FLANGED CHANNEL SIGN POST	675.301	–
						124	124	M	SQUARE TUBE SIGN POST AND ANCHOR	675.341	–
									***** END OPTION ITEMS *****		
						230	230	KG	TUBULAR STEEL SIGN POSTS	675.33	4
						4	4	EA	FOUNDATION FOR TUBULAR STEEL POST	675.43	
						77	77	EA	REMOVING SIGNS	675.50	
						1	1	EA	TEMPORARY TRAFFIC SIGNAL SYSTEM	678.40	

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		TEMPORARY EROSION CONTROL
40	CM	TRENCH EXCAVATION OF EARTH
200	CM	SUBBASE OF DENSE GRADED CRUSHED STONE
20	CM	STONE FILL, TYPE I
180	SM	GEOTEXTILE FOR SILT FENCE
10	KG	SEED–WINTER RYE
1	T	HAY MULCH
100	EA	HAY BALES FOR EROSION CONTROL
85	SM	EROSION MATTING

PROJECT NAME : JAMAICA

PROJECT NO. : BRF 013-1(8)

DESIGN FILE NAME:
IPARM FILE NAME:
SURVEYED BY:
SQUAD LEADER:

PLOT DATE:
SURVEY DATE:
DRAWN BY: SMC
SHEET: 9 OF 116