STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA.	WIDTH (MM)	HEIGHT (MM)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL KG/M 1.7	3.0	4.5	SQUARE STEEL (MM) KG/M 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (MM) KG/M 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (MM) FOUND-ATION	KG/M 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 MM	750 MM	WEIGHT	POST SIZE	SIGN FRAMED REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
																																	W13-1		
STA 5+660 LT	WARDSBORO 5	1	1800	250	0.45						2			X 4.27		X																	D1-1a		E-123M
	WILMINGTON 24	1	1800	250	0.45																														E-123M
STA 5+700 LT	SPEED LIMIT 40	1	600	750	0.45						1			X 4.27		X																	R2-1		E-142M
STA 5+700 RT	NORTH NORTH SOUTH	3	600	300	0.54						2												2	X 3.58 3.43								X	M3-1 M3-1 M3-1		E-136BM
	VERMONT 30 VERMONT 100 VERMONT 30	2 1	600 750	600 600	0.72 0.45																												M1-5 M1-5 M1-5		E-136BM
	← ← →	3	525	375	0.60																												M6-1 M6-1 M6-1		E-136BM
STA 5+762 RT	STOP	1	750	750	0.56						1			X 4.27																					
STA 5+729 LT	SOUTH	1	600	300	0.18						1			X 4.27		X																	M3-3		E-136BM
	VERMONT 100	1	750	600	0.45																												M1-5		E-136BM
TH 56 STA 0+040 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X 4.27		X																	VR-017		E-141M
TH 41 STA 0+120 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X 4.27		X																	VR-017		E-141M
TH 43 STA 0+220 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X 4.27		X																	VR-017		E-141M
VT ROUTE 100/30 STA 3+907 RT	JCT	1	525	375	0.20						1			X 4.27		X																	M2-1		E-136BM
	VERMONT 100	1	750	600	0.45																												M1-5		E-136BM
STA 3+926 LT	TOWNSHEND 6	1	1800	250	0.45						2			4.27 X 4.88		X																	D1-1a		E-123M
	BRATTLEBORO 23	1	1800	250	0.45																												D1-1a		E-123M
												m	m	m 47.58 ~~40~~	m	m 40	m		EA	kg	kg	kg		kg 79.2 ~~113~~	kg	kg	kg								
TOTALS					m 2 7.75 ~~7.19~~	m 2	EA.	m 2				m ~~40~~ 47.58			m 40					kg			EA. 2	kg ~~113~~ 79.2				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT : JAMAICA	PROJECT NO. : BRF 013-1(8)
DESIGN FILE NAME:	
IPARM FILE NAME:	PLOT DATE:
SURVEYED BY: CLD	SURVEY DATE:
SQUAD LEADER: JAW	DRAWN BY: SMC
	SHEET: 49 OF 116