STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (MM)	HEIGHT (MM)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL KG/M 1.7	3.0	4.5	SQUARE STEEL (MM) KG/M 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	NEW SIGN POSTS: TUBULAR ALUMINUM Ø (MM) KG/M 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (MM) KG/M FOUND-ATION	75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 MM	750 MM	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
STA 3+968 RT	↑ JAMAICA 3	1	1800	250	0.45						2			X 4.88		X																	D1-1a		E-123M
	↑ STRATTON MTN SKI AREA 10	1	1800	250	0.45																												D1-1a		E-123M
	← WARDSBORO 5	1	1800	250	0.45																												D1-1a		E-123M
	← WILMINGTON 24	1	1800	250	0.45																												D1-1a		E-123M
STA 3+987 LT	SOUTH	1	600	300	0.18						1			X 4.27		X																	M3-3		E-136BM
	VERMONT 30	1	600	600	0.36																												M1-5		E-136BM
STA 4+029 RT	SOUTH NORTH NORTH	3	600	300	0.54						2											2	X 3.45 3.99								X	M3-3 M3-1 M3-1		E-136BM
	VERMONT 100 VERMONT 30 VERMONT 100	2 1	750 600	600 600	0.90 0.36																												M1-5 M1-5 M1-5		E-136BM
	← ↑ ↑	3	525	375	0.60																												M6-1 M6-3 M6-3		E-136BM
STA 4+034 RT	↔	1	1200	600	0.72						2			X 3.35		X																	W1-7		E-152M
STA 4+064 RT	NORTH NORTH	2	600	300	0.36						1			X 4.27		X															X	M3-1 M3-1		E-136BM
	VERMONT 30 VERMONT 100	1 1	600 750	600 600	0.36 0.45									X 4.88																		M1-5 M1-5		E-136BM
STA 5+280 LT	SPEED LIMIT 40	1	600	750	0.45																											MISSING		
STA 4+079 LT	SOUTH SOUTH	2	600	300	0.36						2			X 4.88		X															X	M3-3 M3-3		E-136BM
	VERMONT 30 VERMONT 100	1 1	600 750	600 600	0.36 0.45																											M1-5 M1-5		E-136BM
	↑ →	2	525	375	0.40																											M6-3 M6-1		E-136BM
STA 5+280 RT	SPEED LIMIT 50	1	600	750	0.45						1			X 4.27																		DAMAGED		
												m	m	m 25	m	m 25	m		EA	kg	kg	kg		kg 84.1 ~~113~~	kg	kg	kg							
TOTALS					m 2 9.10 ~~8.20~~	m 2	EA.	m 2				m 48.18 ~~25~~			m 25					kg			EA. 2	kg 84.1 ~~113~~				EA.	EA.	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT : JAMAICA	PROJECT NO. : BRF 013-1(8)
DESIGN FILE NAME:	
IPARM FILE NAME:	PLOT DATE:
SURVEYED BY: CLD	SURVEY DATE:
SQUAD LEADER: JAW	DRAWN BY: SMC
	SHEET: 50 OF 116