STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

FIRST Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (MM)	HEIGHT (MM)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL KG/M 1.7	3.0	4.5	SQUARE STEEL (MM) KG/M 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (MM) KG/M 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (MM) FOUNDATION	KG/M 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 MM	750 MM	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
STA 4+127 RT	JAMAICA 3	1	1800	250	0.45						2			X 4.27		X																	D1-1a		E-123M
	STRATTON MTN SKI AREA 10	1	1800	250	0.45																												D1-1a		E-123M
STA 4+140 LT	↑ TOWNSHEND 6	1	1800	250	0.45						2	USED EXISTING POSTS		X		X																D1-1a		E-123M
	↑ BRATTLEBORO 23	1	1800	250	0.45																												D1-1a		E-123M
	WARDSBORO 5 →	1	1800	250	0.45																												D1-1a		E-123M
	WILMINGTON 24 →	1	1800	250	0.45																												D1-1a		E-123M
STA 4+209 LT	JCT	1	525	375	0.20						1			X 4.27		X																M2-1		E-136BM
	VERMONT 100	1	750	600	0.45																												M1-5		E-136BM
		SUBTOTAL SHEET 51			3.35									~~15~~ 12.81		~~15~~																			
		SUBTOTAL SHEET 48			6.48									44		~~44~~ 45.14																			
		SUBTOTAL SHEET 49			~~7.19~~ 7.75									40		~~40~~ 47.58									2	~~113~~ 79.2									
		SUBTOTAL SHEET 50			~~8.20~~ 9.10									25		~~25~~ 48.18									2	~~113~~ 84.1									
		SUBTOTAL SHEET 51			3.35									15		~~15~~ 2.81																			
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."												m	m	m 124	m	m 124	m		EA	kg	kg	kg		kg 163.3 ~~226~~	kg	kg	kg								
	PROJECT TOTALS				m 2 26.68 ~~25.22~~	m 2	EA.	m 2				m 124			FROM BK IA m 153.6 ~~124~~						kg			EA. 4	kg 163.3 ~~226~~				EA.	EA.	kg					

DIFF. IN ROUNDING W/ BK IA

PROJECT : JAMAICA	PROJECT NO. : BRF 013-1(8)
DESIGN FILE NAME:	
IPARM FILE NAME:	PLOT DATE:
SURVEYED BY: CLD	SURVEY DATE:
SQUAD LEADER: JAW	DRAWN BY: SMC
	SHEET: 51 OF 116