

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES				
						ROADWAY	EROSION CONTROL	NON-PART.	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS	
														BEGIN OPTION AA						
						40					40		LF	18" CAAP .060 (2-2/3 X 1/2)	601.0215					
						40					40		LF	18" PCCSP .079 (2-2/3 X 1/2)	601.0416					
						40					40		LF	18" RCP CLASS III	601.0815					
						40					40		LF	18" CPEP(SL)	601.2615					
														END OPTION AA						
						2					2		EACH	18" CPEPES	601.7015					
						3					3		EACH	PRECAST REINFORCED CONCRETE DROP INLET WITH CAST IRON GRATE	604.18					
						333					333		LF	6 INCH UNDERDRAIN PIPE	605.10					
						1					1		EACH	UNDERDRAIN FLUSHING BASIN	605.95					
						1					1		MGAL	DUST CONTROL WITH WATER	609.10					
							535				535		CY	STONE FILL, TYPE II	613.11					
						335					335		LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28					
						170					170		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10					
						9					9		SF	DETECTABLE WARNING SURFACE	618.30					
						2					2		EACH	STEEL MARKER POSTS	619.16					
						265					265		LF	BOX BEAM GUARDRAIL (COATED BLACK)	621.30					
						384					384		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80					
								2			2		EACH	ADJUST ELEVATION OF VALVE BOX	629.20					
								95			95		TON	CRUSHED STONE BEDDING	629.54					
						120					120		HR	FLAGGERS	630.15					
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10					
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16					
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17					
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26					
						1					1		LS	MOBILIZATION/DEMobilIZATION	635.11					
						1					1		LS	TRAFFIC CONTROL	641.10					
						14					14		DAY	PORTABLE CHANGEABLE MESSAGE SIGN RENTAL	641.17					
						1750					1750		LF	DURABLE 4 INCH WHITE LINE	646.400					
						1825					1825		LF	DURABLE 4 INCH YELLOWLINE	646.410					
						15					15		LF	DURABLE 24 INCH STOP BAR	646.480					
						46					46		EACH	LINE STRIPING TARGETS	646.76					
							980				980		SY	GEOTEXTILE UNDER STONE FILL	649.31					
							380				380		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515					
							16				16		LB	SEED	651.15					
							135				135		LB	FERTILIZER	651.18					
							1				1		TON	AGRICULTURAL LIMESTONE	651.20					
							1				1		TON	HAY MULCH	651.25					
							8				8		CY	TOPSOIL	651.35					
							800				800		SY	GRUBBING MATERIAL	651.40					

PROJECT NAME: MIDDLEBURY  
 PROJECT NUMBER: RS 0174(8)  
 FILE NAME: z78f21705\_R.dgn  
 PROJECT LEADER: M.A. COLGAN  
 DESIGNED BY: E.A.FIALA  
 QUANTITY SHEET #2  
 PLOT DATE: 8/29/2013  
 DRAWN BY: C.L. CILLEY  
 CHECKED BY: C.S. GOODRICH  
 SHEET 10 OF 104

