



PLAN  
SCALE 1" = 20'-0"  
20 0 20

- NOTES:**
1. THESE PLANS SHOW A CONCEPTUAL EROSION CONTROL PLAN, THE CONTRACTOR MUST SUBMIT A TEMPORARY EPSC PLAN FOR APPROVAL.
  2. TEMPORARY EPSC PLAN MEASURES ARE CONCEPTUALLY SHOWN. THE CONTRACTOR MAY RELOCATE TEMPORARY MEASURES TO IMPROVE EROSION CONTROL WITH APPROVAL OF THE RESIDENT ENGINEER. SILT FENCE SHALL NOT BE INSTALLED ACROSS CONTOURS.
  3. THE CONTRACTOR SHALL USE OTHER TEMPORARY EROSION CONTROL MEASURES AS NECESSITATED BY THE SEQUENCE OF CONSTRUCTION OR AS DIRECTED BY THE RESIDENT ENGINEER.
  4. REFER TO TEMPORARY EROSION CONTROL DETAIL SHEETS FOR ADDITIONAL DETAILS.
  5. SEE SHEET 14, CONVENTIONAL SYMBOLLOGY LEGEND, FOR EPSC LAYOUT PLAN SYMBOLLOGY.

DATUM  
VERTICAL NAVD 88  
HORIZONTAL NAD 83 (92)



PROJECT NAME: MIDDLEBURY  
PROJECT NUMBER: RS 0174(8)  
FILE NAME: z78f217bdr\_ero.dgn PLOT DATE: 8/27/2013  
PROJECT LEADER: M.A. COLGAN DRAWN BY: B.J. MASSE  
DESIGNED BY: B.J. MASSE CHECKED BY: K. REINHART  
EPSC CONSTRUCTION SITE PLAN (1 OF 3) SHEET 97 OF 104