



- NOTES:**
1. THESE PLANS SHOW A CONCEPTUAL EROSION CONTROL PLAN, THE CONTRACTOR MUST SUBMIT A TEMPORARY EPSC PLAN FOR APPROVAL.
  2. TEMPORARY EPSC PLAN MEASURES ARE CONCEPTUALLY SHOWN. THE CONTRACTOR MAY RELOCATE TEMPORARY MEASURES TO IMPROVE EROSION CONTROL WITH APPROVAL OF THE RESIDENT ENGINEER. SILT FENCE SHALL NOT BE INSTALLED ACROSS CONTOURS.
  3. THE CONTRACTOR SHALL USE OTHER TEMPORARY EROSION CONTROL MEASURES AS NECESSITATED BY THE SEQUENCE OF CONSTRUCTION OR AS DIRECTED BY THE RESIDENT ENGINEER.
  4. REFER TO TEMPORARY EROSION CONTROL DETAIL SHEETS FOR ADDITIONAL DETAILS.
  5. SEE SHEET 14, CONVENTIONAL SYMBOLY LEGEND, FOR EPSC LAYOUT PLAN SYMBOLY.

DATUM  
 VERTICAL NAVD 88  
 HORIZONTAL NAD 83 (92)

PLAN  
 SCALE 1" = 20'-0"



PROJECT NAME: MIDDLEBURY  
 PROJECT NUMBER: RS 0174(8)  
 FILE NAME: z78f217bdr\_ero.dgn PLOT DATE: 8/27/2013  
 PROJECT LEADER: M.A. COLGAN DRAWN BY: B.J. MASSE  
 DESIGNED BY: B.J. MASSE CHECKED BY: K. REINHART  
 EPSC CONSTRUCTION SITE PLAN (3 OF 3) SHEET 99 OF 104