

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
				ROADWAY	TRAINING	LANDSCAPING	EROSION CONTROL	BRIDGE	FULL C. E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								15		15		EACH	BEARING DEVICE ASSEMBLY, ELASTOMERIC PAD	531.11				
								90		90		CY	CONCRETE, CLASS C	541.30				
													BEGIN OPTION AA					
				183						183		LF	18" CAAP .105 (2-2/3 X 1/2)	601.0217				
				183						183		LF	18" PCCSP .079 (2-2/3 X 1/2)	601.0416				
				183						183		LF	18" CPEP	601.0915				
													END OPTION AA					
													BEGIN OPTION BB					
				3						3		EACH	18" CSPES .064 (2-2/3 X 1/2)	601.6015				
				3						3		EACH	18" CAAPES .060 (2-2/3 X 1/2)	601.6215				
				3						3		EACH	18" CPEPES	601.7015				
													END OPTION BB					
				1						1		EACH	PRECAST REINFORCED CONCRETE PIPE DI WITH CAST IRON GRATE	604.25				
				10						10		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25				
				1						1		MGAL	DUST CONTROL WITH WATER	609.10				
							15			15		CY	STONE FILL, TYPE I	613.10				
								42		42		CY	STONE FILL, TYPE II	613.11				
								1500		1500		CY	STONE FILL, TYPE IV	613.13				
				160						160		LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28				
				1						1		EACH	RELOCATE MAILBOX, SINGLE SUPPORT	617.10				
				4						4		EACH	STEEL MARKER POSTS	619.16				
				285						285		LF	CHAIN-LINK FENCE, 6 FEET	620.12				
				50						50		LF	GATE FOR CHAIN-LINK FENCE, 6 FEET	620.16				
				11						11		EACH	BRACING ASSEMBLY FOR CHAIN-LINK FENCE, 6 FEET	620.21				
				320						320		LF	REMOVAL OF EXISTING FENCE	620.55				
				362.5						362.5		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20				
				4						4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
				4						4		EACH	GUARDRAIL APPROACH SECTION, GALVANIZED NETC 2 RAIL	621.72				
				301						301		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
												1	LS	FIELD OFFICE, ENGINEERS	631.10			
												1	LS	TESTING EQUIPMENT, CONCRETE	631.16			
												1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17			
												1	LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25			
					520					520		HR	EMPLOYEE TRAINEESHIP	634.10				
				1						1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
				3000						3000		LF	4 INCH WHITE LINE	646.20				
				3000						3000		LF	4 INCH YELLOW LINE	646.21				
				14						14		LF	DURABLE 24 INCH STOP BAR	646.480				
				567						567		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11				
								1575		1575		SY	GEOTEXTILE UNDER STONE FILL	649.31				