



4 - INT CROSSFRAMES TYPE3 ~ 14CF1
LOOKING UPSTATION

4 - INT CROSSFRAMES TYPE3 ~ 14CF2
LOOKING UPSTATION

| ABM INFO | | BILL OF MATERIAL | | | | JOB NO. | DRAWING NO. | REV. | |
|----------|------|------------------|-----|------|-----------------------|---------------------|-------------|------|----------------------|
| PAGE | LINE | MARK | QTY | MARK | MATERIAL | LENGTH FT INCHES | REMARKS | WT | PROCUREMENT NOTES |
| | | 14CF1 | 4 | | INT CROSSFRAMES | | | 276 | |
| 4 | B | a14 | 4 | | L 3 1/2 x 3 1/2 x 3/8 | 5 1 1/2 | M270-50W | | |
| 4 | C | b14 | 4 | | L 3 1/2 x 3 1/2 x 3/8 | 7 2 1/4 | M270-50W | | |
| 4 | C | c14 | 4 | | L 3 1/2 x 3 1/2 x 3/8 | 7 2 1/4 | M270-50W | | |
| 4 | D | m1n | 8 | | PL 1/2 x 12 1/2 | 1 1 1/2 | M270-50W | | |
| 4 | E | m1p | 8 | | PL 1/2 x 11 1/4 | 1 1 1/2 | M270-50W | | |
| 4 | F | m1s | 4 | | PL 1/2 x 5 | 0 5 | M270-50W | | |
| | | 14CF2 | 4 | | INT CROSSFRAMES | | | 276 | |
| 4 | B | a14 | 4 | | L 3 1/2 x 3 1/2 x 3/8 | 5 1 1/2 | M270-50W | | |
| 4 | C | b14 | 4 | | L 3 1/2 x 3 1/2 x 3/8 | 7 2 1/4 | M270-50W | | |
| 4 | C | d14 | 4 | | L 3 1/2 x 3 1/2 x 3/8 | 7 2 1/4 | M270-50W | | |
| 4 | D | m1n | 8 | | PL 1/2 x 12 1/2 | 1 1 1/2 | M270-50W | | |
| 4 | E | m1p | 8 | | PL 1/2 x 11 1/4 | 1 1 1/2 | M270-50W | | |
| 4 | F | m1s | 4 | | PL 1/2 x 5 | 0 5 | M270-50W | | |

NOTES:
FOR GENERAL NOTES SEE DRAWING GNI.

| | | | | | | |
|---|------|------------------------|-----|---------------|---------------|-------------|
| REV. | DATE | REMARKS | DWN | CHK | APVL | SHOP |
| 0 | | | | | | |
| MATERIAL: | | SURFACE PREP. & PAINT: | | HOLES: | | SHOP BOLTS: |
| M270-50W (UN) | | SEE GNI | | 15/16" Ø U.N. | | NONE |
| DESCRIPTION: INTERMEDIATE CROSSFRAMES | | | | | | |
| CASCO BAY STEEL STRUCTURES, INC. 75 SPRING HILL ROAD SACO, MAINE 04072 PHONE (207) 282-7360 FAX. (207) 282-1179 | | | | | | |
| STRUCTURE: US RTE 2 OVER WINOOSKI RIVER WASHINGTON COUNTY, VT | | | | DRAWN: | DATE: | |
| | | | | TS | 08/17 | |
| | | | | CHKD: | DATE: | |
| | | | | PCP | 08/19 | |
| LOCATION: TOWNS OF MORETOWN ~ MIDDLESEX, VT | | | | JOB NO. | DWG NO. | |
| PROJ NO. BRS 0284(14) | | | | 421-1 | 14 | |
| CUSTOMER: WINTERSET INC. | | | | | REV. Δ | |