QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

				LANDSCAPING	FULL E&C ITEMS	UTILITIES NON-FED & NON-STATE PARTIC.	NON-GOVT. PARTIC.	TRAINING	EROSION CONTROL	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
					1							1	LS	FIELD OFFICE – ENGINEERS	631.10	
					1							1	LS	TESTING EQUIPMENT – CONCRETE	631.16	
					1							1	LS	TESTING EQUIPMENT – BITUMINOUS (MOD)	631.17	
					1							1	LS	TESTING EQUIPMENT – PROTECTIVE COATINGS	631.18	
					1							1	LU	FIELD OFFICE – TELEPHONE (NOT A BID ITEM)	631.25	
								1040				1040	HR	EMPLOYEE TRAINEESHIP	634.10	
											1	1	LS	MOBILIZATION	635.10	
											1	1	LS	TRAFFIC CONTROL	641.10	
											1600	1600	LF	DURABLE 4" WHITE LINE	646.40	0
											1600	1600	LF	DURABLE 4" YELLOW LINE	646.41	0
											3300	3300	LF	TEMPORARY 4" WHITE LINE	646.60	0
											3300	3300	LF	TEMPORARY 4" YELLOW LINE	646.61	0
											25	25	EA	LINE STRIPING TARGETS	646.76	5
											1140	1140	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	EST
									310	1760	490	2560	SY	GEOTEXTILE UNDER STONE FILL	649.31	16
									650			650	SY	GEOTEXTILE FOR SILT FENCE	649.51	EST
									200			200	SY	GEOTEXTILE FOR FILTER CURTAINS	649.61	EST
									80			80	LB	SEED	651.15	EST
									5			5	LB	SEED – WINTER RYE	651.17	EST
									450			450	LB	FERTILIZER	651.18	EST
				0.2					2			2.2	TON	AGRICULTURAL LIMESTONE	651.20	EST
				0.2					3			3.2	TON	HAY MULCH	651.25	EST
									30			30	EA	HAY BALES FOR EROSION CONTROL	651.26	EST
				40								40	CY	CEDAR BARK MULCH	651.27	0
											60	60	CY	TOPSOIL	651.35	2
									130	975		1105	SY	GRUBBING MATERIAL	651.40	12
									1			1	LS	EROSION PREVENTION & SEDIMENT CONTROL PLAN	652.10	
									550			550	HR	MONITORING EROSION PREVENTION & SEDIMENT CONTROL PLAN	652.20	
									1			1	LU	MAINTENANCE OF EROSION PREVENTION & SEDIMENT CONTROL PLAN	652.30	
									1700			1700	SY	EROSION MATTING	654.10	11
				4								4	EA	DECIDUOUS TREES (Serviceberry)	656.30	
				5								5	EA	DECIDUOUS TREES (Green Ash)	656.30	
				61								61	EA	DECIDUOUS SHRUBS (Red Stem Dogwood)	656.35	
				40								40	EA	DECIDUOUS SHRUBS (Silky Dogwood)	656.35	
				36								36	EA	DECIDUOUS SHRUBS (Highbush Cranberry)	656.35	
				47								47	EA	DECIDUOUS SHRUBS (Arrowood)	656.35	
											171	171	SF	TRAFFIC SIGNS, TYPE A	675.20	0.99
														*** BEGIN OPTION ITEMS ***		
											350	350	LF	FLANGED CHANNEL SIGN POSTS	675.301	5
											350	350	LF	SQUARE TUBE SIGN POSTS AND ANCHOR	675.341	5
														*** END OPTION ITEMS ***		
											350	350	LB	TUBULAR STEEL SIGN POSTS	675.33	8
											3	3	EA	FOUNDATION FOR TUBULAR STEEL POSTS	675.43	0
											47	47	EA	REMOVING SIGNS	675.50	0
											2	2	EA	ERECTING SALVAGED SIGNS	675.60	0

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		TEMPORARY EROSION CONTROL
15	CY	TRENCH EXCAVATION OF EARTH
80	CY	SUBBASE OF CRUSHED GRAVEL (COARSE GRADED) (MOD)
10	CY	STONE FILL, TYPE I
70	SY	GEOTEXTILE FOR SILT FENCE
5	LB	SEED – WINTER RYE
1	TON	HAY MULCH
30	EA	HAY BALES FOR EROSION CONTROL
30	SY	EROSION MATTING
		TEMPORARY 4" WHITE LINE
800	LF	STA 124+50 TO 132+50 LT
800	LF	STA 124+50 TO 132+50 RT
1700	LF	DETOUR
0	LF	ROUNDING
3300	LF	TOTAL
		TEMPORARY 4" YELLOW LINE
1600	LF	STA 124+50 TO 132+50
1700	LF	DETOUR
0	LF	ROUNDING
3300	LF	TOTAL

PROJECT NAME ROYALTON
PROJECT NUMBER BRS 0147(5)S