STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75	2.0	2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	4.0	4.0 MOD	TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft 3.0	3.5	4.0	5.0	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												1.3	1.7	1.7										7.6	9.0	10.8	14.6								
												OPTION ITEMS																							
STA 122+16 LT	SOUTH	1	24"	12"	2.00						1			X			X	X															M3-3		E-136B
	VERMONT 14	1	24"	24"	4.00																												M1-5A		E-136B
STA 123+00 LT	CHELSEA ST	1					1																										SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED PERPENDICULAR TO TOP OF POST FOR THE EXISTING STOP SIGN		
STA 123+81 RT		1	30"	30"	6.25						1			X			X	X															W11-2 FLORESCENT YELLOW AND GREEN SHEETING		E-152
		1	24"	12"	2.00																												W16-7 FLORESCENT YELLOW AND GREEN SHEETING	32-D	
REV 123+85 LT	SOUTH NORTH	2	24"	12"	4.00						1												X	X							X		M3-3 M3-1		E-136B
	VERMONT 14 VERMONT 14	1 1	24" 24"	24" 24"	4.00 4.00																												M1-5A M1-5A		E-136B
		2	21"	15"	4.38																												M6-1L M6-1R		E-136B
STA 123+89 LT		1	30"	30"	6.25						1			X			X	X															W11-2 FLORESCENT YELLOW AND GREEN SHEETING		E-152
		1	24"	12"	2.00																												W16-7 FLORESCENT YELLOW AND GREEN SHEETING	32-D	
STA 124+14 RT	NORTH	1	24"	12"	2.00						1			X			X	X															M3-1		E-136B
	VERMONT 14	1	24"	24"	4.00																												M1-5A		E-136B
												FT	FT	FT	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB								
														60			60							114.0											
TOTALS			SF 44.88	SF	EA. 1	SF						FT 60			FT 60					LB			EA. 1	LB 114.0				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: ROYALTON	PROJECT NO. : BRS 0147(5)S
DESIGN FILE NAME: 91298SGN.dwg	
IPARM FILE NAME:	PLOT DATE:
SURVEYED BY: CLD	SURVEY DATE:
SQUAD LEADER: KEB	DRAWN BY: TJS
	SHEET: 32-B OF 76