

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
						ROADWAY	TRAINING	EROSION CONTROL	BRIDGE	Full C&E	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
														BEGIN OPTION BB					
						93					93		LF	24" CAAP .060 (2-2/3 X 1/2)	601.0225				
						93					93		LF	24" PCCSP .064 (2-2/3 X 1/2)	601.0425				
						93					93		LF	24" CPEP	601.0920				
														END OPTION BB					
						1					1		EACH	PRECAST REINFORCED CONCRETE CATCH BASIN WITH CAST IRON GRATE	604.20				
						245					245		CY	STONE FILL, TYPE I	613.10				
						176					176		CY	STONE FILL, TYPE III	613.12				
									750		750		CY	STONE FILL, TYPE IV	613.13				
						1					1		EACH	RELOCATE MAILBOX, SINGLE SUPPORT	617.10				
						1					1		EACH	RELOCATE MAILBOX, MULTIPLE SUPPORT	617.12				
						230					230		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10				
						672					672		LF	BOX BEAM GUARDRAIL	621.30				
						2					2		EACH	MANUFACTURED TERMINAL SECTION, TANGENT	621.51				
						561					561		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
						200					200		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
						2250					2250		HR	FLAGGERS	630.15				
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
							520				520		HR	EMPLOYEE TRAINEESHIP	634.10				
						1					1		LS	MOBILIZATION/DEMobilIZATION	635.11				
						1					1		LS	TRAFFIC CONTROL	641.10				
						1					1		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
						2510					2510		LF	DURABLE 4 INCH WHITE LINE	646.400				
						2510					2510		LF	DURABLE 4 INCH YELLOW LINE	646.410				
						15					15		LF	DURABLE 24 INCH STOP BAR	646.480				
						1000			300		1300		SY	GEOTEXTILE UNDER STONE FILL	649.31				
								330			330		SY	GEOTEXTILE FOR SILT FENCE	649.51				
								210			210		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
								670			670		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
								70			70		LB	SEED	651.15				
								10			10		LB	SEED, WINTER RYE	651.17				
								590			590		LB	FERTILIZER	651.18				
								3			3		TON	AGRICULTURAL LIMESTONE	651.20				
								3			3		TON	HAY MULCH	651.25				
								610			610		CY	TOPSOIL	651.35				
								238			238		SY	GRUBBING MATERIAL	651.40				
								1			1		LS	EPSC PLAN	652.10				

PROJECT NAME: WARREN
 PROJECT NUMBER: BR 013-4 (14)
 FILE NAME: s78f242forms.dgn
 PROJECT LEADER: J. LACROIX
 DESIGNED BY: U. STANLEY
 QUANTITY SHEET 2
 PLOT DATE: 27-JUL-2012
 DRAWN BY: M. LONGSTREET
 CHECKED BY: J. GRFFIN
 SHEET 10 OF 83