

PROJECT LENGTHS AND ITEM QUANTITIES

ITEM DESCRIPTION
 NOTLAND
 OVERLAY DEPTH
 GRAVEL SHOULDERS
 GRAVEL SHOULDERS
 EMULSIFIED ASPHALT
 BITUMINOUS CONCRETE PAVEMENT
 OR TYPE 1
 ALL PORE FROM RENTAL
 UNIFORM TRAFFIC OFFICERS
 TEMP. PAVT. M
 FORTIFICATION
 UNIFORM TRAFFIC OFFICERS
 TEMP. PAVT. M

ITEM NUMBER	UNIT	FEET	FT INCH	G.Y. TON	CWT	TON	EA	IIR	IIR	IIR	IIR	LS	L.F.	REMARKS
ESSEX MM 4.528 ~ MM 5.268		3907	24 1/2		26	242								LEVEL COURSE @ 300 TON/MI. 1 1/2" WEAR COURSE 3" GRAVEL SHOULDERS
ESSEX MM 5.268 ~ MM 5.340		381	46 1		5	0								NO LEVEL COURSE 1" WEAR COURSE
ESSEX MM 5.340 ~ MM 5.416		401	24 1/2		3	25								LEVEL COURSE @ 300 TON/MI. 1 1/2" WEAR COURSE 3" GRAVEL SHOULDERS
ESSEX MM 5.416 ~ MM 5.506		474	24 1/2		3	30								LEVEL COURSE @ 300 TON/MI. 1 1/2" WEAR COURSE 2" PAVED SHOULDERS
ESSEX MM 5.506 ~ MM 5.750		1288	24 1/2		9	80								LEVEL COURSE @ 300 TON/MI. 1 1/2" WEAR COURSE 3" GRAVEL SHOULDERS
DRIVES & APPROACHES						200								
PROJECT (ESTIMATED)														
ROUNDING														
TOTALS		6451		39	4	96	2	5	14	14			23080	
				450	50	2200	10	10	15	70	70	1	23100	

PROJECT Essex NUMBER E EGC-E 030-1025 SHEET 4 OF 14