PROJECT Essex ROUTE Vt. 15 PROJECT NUMBER F EGC-F 030(12)

TEMPORARY 4" REFLECTORIZED YELLOW LINE

MILE	MILE	LT	RT	Quan. Lt.	Quan. ℄	Quan. Rt.	Total L.F.
4.528	5.267	Solid	Solid	3902		3902	7804
5.267	5.381	See Detail Layout Sheet for Durable Markings.					
5.381	5.750	Solid	Solid	1948		1948	
				5850		5850	11,700
	Assume 100% ℄ Lost During Leveling						
		100 X 11,700 =				+	11,700
	4 Town Road openings @ 40'						
	4 X 40 X 2 =					-	320
							23080
					Rounding		20
							23,100

Although not indicated on this sheet, the ℄ shall be broken at all intersecting town highways as shown on the plan detail sheet. The Resident Engineer shall verify the accuracy of pavement markings in the field in accordance with the "Guideline on Markings of Centerlines".

SHEET 7 of 14