

QUANTITY SHEET

**STATE OF VERMONT
AGENCY OF TRANSPORTATION**

BRIDPORT HES-F017-K(2)						SHOREHAM - BRIDPORT - ADDISON F017-K(2)						APPROXIMATE SUMMARY OF QUANTITIES						
NON-GVT PART.	TRAIN.	EROSION CONTROL	ROAD	TOTAL		NON-GVT PART.	TRAIN.	EROSION CONTROL	BR 100	BR 200	ROAD	TOTAL	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING	
											24	24	24	LF	12' CSP .064	601.0005		
											336	336	336	LF	15' CSP .064	601.0010		
			16	16							180	180	196	LF	18' CSP .064	601.0015		
			6	6							68	68	74	LF	24' CSP .064	601.0025		
						44						44	44	44	LF	24' CSP .064 (MODIFIED)	601.0025	
											14	14	14	LF	30' CSP .079	601.0036		
											44	44	44	LF	42' CSP .109	601.0052		
											8	8	8	LF	48' CSP .109	601.0057		
						18						18	18	18	LF	54' CSP .109 (MODIFIED)	601.0062	
											22	22	22	LF	72' CSP .138	601.0078		
											98	98	98	LF	84' CAAP .135 (3' X 1' CORR.)	601.0353		
											48	48	48	LF	18' RCP CLASS III	601.0815		
											60	60	60	LF	24' RCP CLASS III	601.0825		
			12	12									12	LF	30' RCP CLASS III	601.0835		
											20	20	20	LF	36' RCP CLASS III	601.0845		
											400	400	400	LF	17' X 13' CSPA .064	601.3010		
											52	52	52	LF	21' X 15' CSPA .064	601.3015		
											40	40	40	LF	35' X 24' CSPA .079	601.3036		
											86	86	86	LF	42' X 29' CSPA .079	601.3046		
											1	1	1	EA	12' CSP ELBOW .064	601.5005		
											2	2	2	EA	15' CSPES .064	601.6010		
											4	4	4	EA	18' CSPES .064	601.6015		
											1	1	1	EA	24' CSPES .064	601.6025		
											1	1	1	EA	30' CSPES .079	601.6036		
											2	2	2	EA	18' RCPES CLASS III	601.6815		
											3	3	3	EA	24' RCPES CLASS III	601.6825		
											1	1	1	EA	30' RCPES CLASS III	601.6835		
											2	2	2	EA	36' RCPES CLASS III	601.6845		
											1	1	1	EA	35' X 24' CSPAES .079	601.8036		
											2	2	2	EA	42' X 29' CSPAES .079	601.8046		
						34					176	210	210	LF	RELAYING PIPE CULVERTS	601.99	4	
											500	500	500	LF	CLEANING CULVERT PIPE IN PLACE (0 - 24' DIA INCLUSIVE)	601.995	EST.	
											500	500	500	LF	CLEANING CULVERT PIPE IN PLACE (GREATER THAN 24' DIA)	601.996	EST.	

DETAILED SUMMARY OF QUANTITIES			
QUANTITIES	UNIT	ITEMS	
		BITUMINOUS CONCRETE PAVEMENT	
		F017-1(2) HES	
	TYPE I	SUBBASE REPAIR COURSE	
13827	TON	MAINLINE SHOULDER	13146 681
1354	TON	MAINLINE FULL DEPTH	376 978
543	TON	EST. OTHER SUBBASE REPAIR	543
98	TON	VT 125 (EAST)	98
325	TON	VT 125 (WEST)	325
		SUB TOTAL	14065 2082
	TYPE II	OVERLAY COURSE	
5562	TON	SHOREHAM	5562
12320	TON	BRIDPORT	11042 1278
8045	TON	ADDISON	8045
217	TON	VT. 125 (WEST)	217
66	TON	VT. 125 (EAST)	66
379	TON	DRIVES & APPROACHES	286 93
50	TON	EST. DRIVES	50
30	TON	TEMPORARY DETOUR (BRIDGE 18)	30
		SUB TOTAL	25015 1654
	TYPE IV	LEVELLING COURSE	
6254	TON	MAINLINE	6102 152
		SUBTOTAL	6102 152
350	TON	ROUNDING	318 32
		SUB TOTAL OF 3 TYPES	45500 3920
49420	TON	FINAL TOTALS	49420

DESIGN FILE NO. ZG0:150,63183B030.DGN:2
 PRF FILE 83B030Q52
 DRAWN BY LASKOWSKI
 SQUAD LEADER PERKINS
 DATE PLOTTED 1-JAN-1990
 PROJ. NAME SHOREHAM-BRIDPORT-ADDISON F 017-K(2)
 PROJ. NO. BRIDPORT HES F 017-K(2)
 SHEET 8 OF 420 SHEETS
 SHEET 8 OF 477