QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

BRIDPORT HES-F017-1(2)							SHOREHAM - BRIDPORT - ADDISON F017-1(2)							APPROXIMATE SUMMARY OF QUANTITIES					DETAILED SUMMARY OF QUANTITIES		
		NON-GVT PART.	TRAIN.	EROSION CONTROL	ROAD	TOTAL		NON-GVT PART.	TRAIN.	EROSION CONTROL	BR 100	BR 200	ROAD	TOTAL	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING	QUANTITIES	UNIT	ITEMS
																	BEGIN OPTION BID ITEMS					
					54	54							352	352	406	LF	15'' CSP .064	601.0010				
					54	54							352	352	406	LF	15'' RCP CLASS III	601.0810				
													50	50	50	LF	18'' CSP .064	601.0015				
													50	50	50	LF	18'' RCP CLASS III	601.0815				
					168	168							84	84	252	LF	18'' CAAP .060	601.0215				
					168	168							84	84		LF	18'' PCCSP .064	601.0415				
					144	144									144	LF	24'' CSP .064	601.0025				
					144	144									144	LF	24'' RCP CLASS III	601.0825				
													62	62	62	LF	24'' CAAP .060	601.0225				
													62	62	62	LF	24'' PCCSP .064	601.0425				
													80	80	80	LF	24'' CAAP .060	601.0225				
													80	80	80	LF	24'' PCCSP .064	601.0425				
													80	80	80	LF	24'' RCP CLASS III	601.0825				
													80	80	80	LF	36'' CAAP .075	601.0246				
													80	80	80	LF	36'' PCCSP .079	601.0446				
													98	98	98	LF	36'' CAAP .105	601.0247				
													98	98	98	LF	36'' PCCSP .079	601.0446				
													110	110	110	LF	54'' CAAP .105	601.0262				
													110	110	110	LF	54'' PCCSP .109	601.0462				
					2	2									2	EA	18'' CSPES .064	601.6015				
					2	2									2	EA	18'' CAAPES .060	601.6215				
					1	1									1	EA	24'' CSPES .064	601.6025				
					1	1									1	EA	24'' RCPES CLASS IIII	601.6825				
													2	2	2	EA	36'' CSPES .079	601.6046				
													2	2	2	EA	36'' CAAPES .075	601.6246				
																	END OPTION BID ITEMS					
													4	4	4	CY	CEMENT RUBBLE MASONRY	602.15	0.8			
					1	1							6	6	7	EA	CHANGE ELEVATION OF DI, CB, OR MH	604.40				
					1	1							3	3	4	EA	CAST IRON GRATE W/FRAME TYPE A	604.45				
					1	1							4	4	5	EA	CAST IRON GRATE W/FRAME TYPE B	604.46				
													1	1	1	EA	CAST IRON COVER W/FRAME	604.50				
													1	1	1	EA	CAST IRON GRATE W/FRAME TYPE D	604.51				
													1000	1000	1000	LF	6'' UNDERDRAIN	605.10				
													300	300	300	LF	6'' UNDERDRAIN CARRIER PIPE	605.20				
													5	5	5	EA	UNDERDRAIN FLUSHING BASIN	605.95				
					76	76							54	54	130	HR	ROADWAY PATROL MAINTENANCE	607.10	EST.			
					10	10							10	10	20	HR	BULLDOZER RENTAL, TYPE I	608.10	EST.			
					6	6							94	94	100	HR	POWER GRADER RENTAL	608.15	EST.			
				5		5				65			90	155	160	HR	ALL PURP. EXCAVATOR RENTAL, TYPE I	608.25	3			
					10	10							400	400	410	HR	POWER BROOM RENTAL	608.30	EST.			
				5		5				65			90	155	160	HR	TRUCK RENTAL	608.37	3			
					544	544							9006	9006	9550	MGL	DUST CONTROL W/WATER	609.10	EST.			

DESIGN FILE NO. ZG0:150,63383B030.DGN;2
PRF FILE 83B0300S3
DRAWN BY LASKOWSKI
SQUAD LEADER PERKINS
DATE PLOTTED 1-JAN-1990
PROJ. NAME SHOREHAM-BRIDPORT-ADDISON F 017-1(2)
PROJ. NO. BRIDPORT HES F 017-1(2)