QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

BRIDPORT HES-F017-I(2)							SHOREHAM - BRIDPORT - ADDISON F017-I(2)							APPROXIMATE SUMMARY OF QUANTITIES				
		NON-GVT PART.	TRAIN.	EROSION CONTROL	ROAD	TOTAL	NON-GVT PART.	TRAIN.	EROSION CONTROL	BR 100	BR 200	ROAD	TOTAL	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
					4	4						66	66	70	TON	DUST AND ICE CONTROL W/CALC. CHLORIDE	609.15	EST.
				221		221			1349				1349	1570	CY	STONE FILL, TYPE I	613.10	11
				7		7			253	300	90		643	650	CY	STONE FILL, TYPE II	613.11	8
					206	206						454	454	660	LF	CAST IN PLACE CEMENT CONCRETE CURB, TYPE A	616.27	3
					115	115								115	LF	CAST IN PLACE CEMENT CONCRETE CURB, TYPE B	616.28	
												50	50	50	TON	BITUMINOUS CONCRETE SURFACE FOR GUTTERS AND TRAFFIC ISLANDS	616.47	
					4	4						76	76	80	EA	RELOCATE MAILBOX, SINGLE SUPPORT	617.10	
												1	1	1	EA	RELOCATE MAILBOX, MULTIPLE SUPPORT	617.12	EST.
												4	4	4	SY	PORTLAND CEMENT CONC. SIDEWALK 5''	618.10	
					10	10								10	EA	BOUNDARY MARKERS	619.10	1
					10	10						130	130	140	EA	WOOD MARKER POST	619.15	8
					5	5						20	20	25	EA	REMOVING AND RESETTING PROP. MARKER	619.20	EST.
												8500	8500	8500	LF	REMOVING & RESETTING FENCE	620.50	
							3935					3115	7050	7050	LF	REMOVAL OF EXISTING FENCE	620.55	
												8500	8500	8500	LF	BARBED WIRE FENCE-4STRAND (TEMPORARY)	620.60	
												6550	6550	6550	LF	STEEL BEAM GUARD RAIL	621.20	
												130	130	130	LF	HEAVY DUTY STEEL BEAM GUARD RAIL	621.21	
												26	26	26	EA	BREAKAWAY CABLE TERMINAL	621.50	
												6820	6820	6820	LF	REMOVAL AND DISPOSAL OF GUARD RAIL	621.80	
												90	90	90	EA	REMOVAL AND DISPOSAL OF GUIDE POST	621.81	
										700	800		1500	1500	LF	TEMPORARY TRAFFIC BARRIER	621.90	
					1	1						1	1	2	MBF	INSULATION BOARD	622.10	EST.
												2	2	2	EA	GATE VALVE WITH VALVE BOX	629.27	
												170	170	170	LF	12'' PVC CLASS 150	629.33	
					330	330						4470	4470	4800	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
					730	730						7270	7270	8000	HR	FLAGGERS	630.15	EST.
					0.1	0.1						0.8	0.8	0.9	LS	FIELD OFFICE - ENGINEER	631.10	
					0.1	0.1						0.8	0.8	0.9	LS	TESTING EQUIPMENT - CONCRETE	631.16	
					0.1	0.1						0.8	0.8	0.9	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	
			180			180			1620				1620	1800	HR	EMPLOYEE TRAINEESHIP	634.10	
					0.1	0.1						0.8	0.8	0.9	LS	MOBILIZATION	635.10	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DESIGN FILE NO. Z60:I50,63J83B030.DGN;2
PRF FILE 83B0300S4
DRAWN BY LASKOWSKI
SQUAD LEADER PERKINS
DATE PLOTTED 1-JAN-1990
PROJ. NAME SHOREHAM-BRIDPORT-ADDISON F 017-I(2)
PROJ. NO. BRIDPORT HES F 017-I(2)
SHEET 10 OF 420 SHEETS