

BREAKAWAY CABLE TERMINAL

LT. 99+93 ~ 100+18
103+56 ~ 103+81

RT. 98+81 ~ 99+06
102+43 ~ 102+68

REMOVAL AND DISPOSAL OF GUARD RAIL

77 LT. 02 100+95 ~ 101+20
45 69 101+40 ~ 101+68

77 RT. 01 100+96 ~ 101+20
45 69 101+40 ~ 101+68

CONSTRUCT TEMPORARY DETOUR

99+50 ~ 103+00

B M 1
Chis Corn.
As EL. 500.00

101+27 LT ~ DETOUR
NEW 24" X 18" CSPL 109 (MOD)
(SEE SPECIAL PROVISIONS)
101+37 LT ~ DETOUR
NEW 24" X 20" CSPL 104 (MOD)
(SEE SPECIAL PROVISIONS)
Remove

MAG. CURVE 1939

WIRE FENCE W/ WOOD POSTS
100+00 RT - 105+00 RT

STEEL BEAM GUARD RAIL

LT. 100+18 ~ 103+56
RT. 99+06 ~ 102+43

Removing and Resetting Fence
100+00 RT ~ 102+00 RT

Temporary Barbed Wire Fence (4 Strand)
100+00 RT ~ 102+00 RT

GEOTEXTILE FABRIC

FOR SILT FENCE
100+00 LT ~ 103+00 LT
100+00 RT ~ 103+00 RT

SAND BORROW

101+03 ~ 101+61

REMOVAL OF EXISTING FENCE

LT. 100+00 ~ 106+00 (NON-PART.)
RT. 100+00 ~ 106+00 (NON-PART.)

REV P.T. 100+35.36

STA. 101+27.00
2 7'-0" X 5'-1" CGMPRA
0.109" X 94' LONG
Δ = 90°
(SEE BR 100)

STA. 101+37.00
2 7'-0" X 5'-1" CGMPRA
0.109" X 94' LONG
Δ = 90°
(SEE BR 100)

SHOREHAM 99+00 ~ 104+00

MM 5.49 ~ MM 5.58 (See Sheet 131 of 420)

20'
PLAN SCALE



105
SHOREHAM-BRIDPORT-ADDISON
FOA 7-112
Sheet 131 of 420
SHEET 131 OF 477