F.A.S. 1940 13 67
18-B(1)

REMOVING & RESETTING FENCE
259+35 – 262+16 Lt.
256+05 – 262+40 Rt.

BREAK AWAY CABLE TERMINAL
248+00 Rt. – 248+25 Rt.
248+00 Lt. – 248+25 Lt.

REMOVAL OF EXISTING FENCE (NON-PART.)
254+55 – 261+50 Rt.

FIELD DRIVE
249+45 Lt.
254+30 Rt.
256+25 Rt.
258+70 Lt. & Rt.
259+75 Rt.
260+00 Lt.

BARBED WIRE FENCE – 4 STRAND
254+55 Rt. – 261+50 Rt.

RELOCATE MAILBOX – SINGLE SUPPORT
248+80 Lt.
255+90 Lt.
248+40 Rt

254 ~~255~~+25 Rt. 15" CMP
Retain NEW 15"x40' CSP

256+25 Rt. 15" CMP
Retain REPLACED w/NEW 15"x40 CSP

258+85 Rt. 18" CGMP
Retain EXTEND INLET & OUTLET 7' EA.

258+95 Rt. ~ 259+45 Rt.
Clean Ditch (To be Paid As All Purpose Excavator Rental & Truck Rental)

259+45 24" ACCGMP
Retain NEW 24"x56' ACCSP

261+90 ~ 262+90 Rt.
Clean Ditch (To be Paid As All Purpose Excavator Rental & Truck Rental)

262+90 18" RCP
Retain & Extend w/New ~~18"x RCP Cl.III~~ @ Outlet
Also Construct 20' Ditch w/12"x6 Stone Pad, Type I @ Outlet
SEE TYPICAL ABOVE
24"x16' ACCSP

BRIDPORT 248+00 ~ 264+00
MM 1.90 ~ MM 2.20

Shoreham – Bridport – ADDISON
F017-1(2)
SHEET 145 OF 420