

<u>Item No.</u>	<u>Description</u>	<u>Unit</u>	<u>Rdwy.</u>	<u>Rounding</u>	<u>Total</u>	<u>Remarks</u>
210.10	Cold Planing - Bituminous Pavement (3/4")	SY	5132	18	5150	
404.65	Emulsified Asphalt	CWT	27	3	30	
406.25	Bituminous Concrete Pavement	Ton Ton	729 231	12	1600	1" wearing course 3/4" Cold Planed Replacement. 1/2" leveling est. shoulders.
604.40	Changing Elev. of D.I. C.B. or M.H. (not a bid Item)	EA	1		1	Est.
608.25	All Purpose Excavator Rental (not a bid item)	HR	1		1	Est.
608.30	Power Broom Rental	HR	10		10	Est.
630.10	Uniformed Traffic Officers	HR	80		80	Est.
630.15	Flagpersons	HR	80		80	Est.
635.10	Mobilization	LS	1		1	
646.35	Temporary 4" Reflectorized White Line	LF	6405	45	6450	
646.36	Temporary 4" Reflectorized Yellow Line	LF	4864	6	4870	
646.60	Durable 4" Reflectorized White Line	LF	1807	3	1810	
646.61	Durable 4" Reflectorized Yellow Line	LF	1100		1100	
646.64	Durable 24" Stop Bar	LF	165		165	
646.65	Durable Arrow Markings	EA	31		31	
646.66	Durable Letter Markings	EA	60		60	
678.22	Vehicle Loop Detector (not a bid item)	LF	1		1	
678.22	Vehicle Loop Detector (Modified)	LF	1742		1742	

Bennington M 1000(7) S