

SEEDING FORMULA, ITEM 651.10  
URBAN AREAS

% WT	LBS/A	NAME	PUR%	GERM%
37.50	30	· CREEPING RED FESCUE (VAR. PENNLAWN)	98	85
31.25	25	KENTUCKY BLUEGRASS (VAR. COMMON)	85	75
31.25	25	PERENIAL RYE GRASS (VAR. PENNFINE)	95	90
<u>100.00</u>	<u>80</u>	<u>LBS/ACRE</u>		

THE SEED MIXTURE SHALL NOT HAVE A WEED CONTENT EXCEEDING 0.40% BY WEIGHT AND SHALL BE FREE FROM ALL NOXIOUS WEED SEED.

HAY MULCH, ITEM 651.25 TO BE PLACED ON ALL EARTH SLOPES AT THE RATE OF TWO TONS PER ACRE

FERTILIZER, ITEM 651.15, SHALL BE MIXED AS FOLLOWS: (SAND FORMULA)

NITROGEN 10%

PHOSPHORUS 20%

POTASH 20%

FERTILIZER SHALL BE DELIVERED IN BAGS NOT TO EXCEED 100LBS EACH AND IS TO BE APPLIED AT RATE OF 500LBS. PER ACRE.

AGRICULTURAL LIMESTONE, ITEM 651.20, TO BE APPLIED TO ALL EARTH SLOPES AT THE RATE OF TWO TONS PER ACRE OR AS DIRECTED BY THE ENGINEER.

TOPSOIL, ITEM 65310 TO BE USED WITH SEED, ITEM 651.10 IN RESIDENTIAL AREAS, AS DIRECTED BY THE ENGINEER.

PROJECT ESSEX

NO M 5400(3)S  
SHEET 10 OF 60