

SEED, ITEM 651.10  
TO BE APPLIED AS DIRECTED BY THE ENGINEER

%WT	LBS/A	NAME	PUR%	GERM%
3.33	2	CROWN VETCH	97	75
50.00	30	CREEPING RED FESCUE	98	85
8.33	5	TIMOTHY	99	85
16.67	10	PERENNIAL RYE GRASS(VAR. PENNFINE)	95	85
8.34	5	ALFALFA (VAR. SARANAC)	99	85
8.33	5	BIRDSFOOT TREFOIL(VAR.EMPIRE)	98	85
5.00	3	HIGHLAND BENT GRASS	92	85
<u>100.00</u>	<u>60</u>	<u>LBS/ACRE</u>		

THE SEED MIXTURE SHALL NOT HAVE A WEED CONTENT EXCEEDING 0.40% BY WEIGHT AND SHALL BE FREE OF ALL NOXIOUS WEED SEED.

MARKER POSTS, (WOOD OR STEEL AS SPECIFIED)  
TO BE PLACED AS DIRECTED BY THE ENGINEER.

FERTILIZER, ITEM 651.15 (STANDARD FORMULA)  
FORMULA 10-20-10 TO BE USED WITH SEED, ITEM 651.10.  
ITEM 651.15 APPLIED AT THE RATE OF 500 LBS/ACRE.

AGRICULTURAL LIMESTONE, ITEM 651.20  
TO BE APPLIED AT RATE OF 2 TONS/ACRE  
OR AS DIRECTED BY THE ENGINEER.

HAY MULCH, ITEM 651.25  
TO BE PLACED ON EARTH SLOPES AT THE RATE OF  
2 TONS/ACRE.

TOPSOIL, ITEM 653.10  
TO BE USED WITH SEED, ITEM 651.10 IN RESIDENTIAL  
AREAS, AS DIRECTED BY THE ENGINEER.