

PROJECT LENGTHS AND ITEM QUANTITIES

ITEM DESCRIPTION	ITEM NUMBER	OPTION													REMARKS
		LENGTH	WIDTH	OVERLAY DEPTH	GRAVEL SHOULDERS	GRAVEL SHOULDERS	EMULSIFIED ASPHALT	BITUMINOUS CONCRETE PAVEMENT	CHANGE ELEV. OF CB, DI, OR MH	ALL PURPOSE EXCAV. RENTAL TYPE I	POWER BROOM RENTAL	UNIFORMED TRAFFIC OFFICERS	FLAGPERSONS MOBILIZATION	TEMP. PAVT.	
UNIT	FEET	FT	INCH	C.Y.	TON	CWT	TON	EA	HR	HR	HR	HR	LS	L.F.	
LOCATION															
ESSEX MM 3.303 ~ MM 4.431	10486	23				67	312								LEVEL 150T/M1
JERICHO MM 0.000 ~ MM 0.858		23	1 1/4				1860								WEAR COURSE
				680	1122										3.5' GRAVEL SHOULDERS
JERICHO MM 0.858 ~ MM 1.057	1052	23				7	0								NO LEVEL IN SLIP AREA -
		23	1 1/4				187								WEAR COURSE TO BE
				68	113										PAVED CONTINUOUS
JERICHO MM 1.057 ~ MM 2.893	9694	23				61	288								LEVEL 150T/M1
		23	1 1/4				1719								WEAR COURSE
				628	1036										3.5' GRAVEL SHOULDERS
RICHMOND MM 0.000 ~ MM 0.748	3950	23				25	196								LEVEL @ 250T/M.
		23	1 1/4				701								WEAR COURSE
				841	1388										3.5' GRAVEL SHOULDERS
DRIVES & APPROACHES				100	165		200								
PROJECT (EST)							50*	2	10	38	139	139	50,361		* FOR CURBS & GUTTERS
ROUNDING				13	21	10	37			2	11	11	39		
TOTALS PAGE	25182			2330	3845	170	5550	2	10	40	150	150	50400		