

NOTE:

If signs and posts are within the shoulder reconstruction area, they shall be relocated according to Standard Sheet E-29 or the M.U.T.C.D. Payment for removing signs and posts shall be Item 675.53 Removing Signs, EA. Payment for reinstalling signs and post shall be Item 675.60 Erecting Salvaged Signs, Type A, S.F. and Item 675.55 Setting Salvaged Posts, EA. If a new post of adequate length is required, Item 675.35, Traffic Sign Posts Type A, LB. Quantities for this work is estimated. Traffic Design personnel will assist the Resident Engineer in sign placement, if requested.

Essex M 5400(3) S
Essex-Jericho-Richmond RS 0224(3)

Sheet 37 of 60