

PC 13170.50
 D = 6°
 Bank 0.42/ft
 (to match existing)

13158 Lt
 Begin Guard Rail (Standard Steel)
 Beam w/ Wood Posts, Type II
 Item 621.28

ROW
 24.75

13150 Lt
 Construct Drive

Note: All Embankment will be Granular
 Borrow, Item 203.32 unless
 labeled otherwise.

102 Curb Sign

13+00-
 M.M. 1.05
 Begin Common Excavation, Item 203.13
 Begin Subbase of Gravel, Item 301.15
 Begin 5" Plant Mixed Base Course Item 303.25
 Begin 1 3/4" Course of Bituminous Concrete Pavement, Type D, Item 406.25

Note: All Material Excavated will be Disposed of
 Off the Site or as Directed by the Engineer.
 Two Way Traffic Will Be Maintained During
 The Hours of Darkness.

