STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (In)	SIGN DIMENSIONS HEIGHT (In)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (In) lb/ft 1.75 1.88	SQUARE STEEL (In) lb/ft 2.0 2.16	SQUARE STEEL (In) lb/ft 2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) lb/ft 3.0 1.3	TUBULAR ALUMINUM Ø (In) lb/ft 4.0 1.7	TUBULAR ALUMINUM Ø (In) lb/ft 4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (In) lb/ft 3.0 7.6	TUBULAR STEEL Ø (In) lb/ft 3.5 9.0	TUBULAR STEEL Ø (In) lb/ft 4.0 10.8	TUBULAR STEEL Ø (In) lb/ft 5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	BELOW GROUND	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
220+~~10~~ 45 LT	SPEED LIMIT 25	1	24	~~30~~ 30	~~5.0~~ 5.0						1			17.			17.																R2-1 REMOVE SIGN INSTALL NEW SIGN		E-142
	THROUGH WAY BEGINS HERE	1	24	24	4.0																												VR-041 REMOVE SIGN INSTALL NEW SIGN		E-141
221+60 RT	END	1	24	12	2.0						1			16.	16.																		M4-6 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-140
	VERMONT 64	1	24	24	4.0																												M1-6 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-136B
223+00 LT	WEST	1	24	12	2.0						1			16.	16.																		M3-4 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-136B
	VERMONT 64	1	24	24	4.0																												M1-6 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-136B
223+60 RT	STOP	1	30	30	6.25						1			15.	15.																		R1-1 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-143
VT 14 STA. 336+48 RT	BARRE 6	1	72	12	6.0						2						38.	X														X	D1-1 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-123
	WEST	1	24	12	2.0																												M3-4 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-136B
	TO	1	24	12	2.0																												M4-5 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-135
	NORTH	1	24	12	2.0																												M3-1 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-136B
	VERMONT 64	1	24	24	4.0																												M1-6 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-136B
	INTERSTATE 89	1	24	24	4.0																												M1-1 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-135
	VERMONT 14	1	24	24	4.0																												M1-6 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-136B
	←	1	21	15	2.19																												M6-1 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-136B
	←	1	21	15	2.19																												M6-1 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-135
	↑	1	21	15	2.19																												M6-3 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-136B
					57.82							FT	FT	FT 64.	FT 47.	FT	FT 55.	EA 2	EA	LB	LB	LB		LB	LB	LB	LB				2 EA				
	SUB TOTALS(1)				SF 57.82	SF	EA.	SF				FT 64.			FT 102.					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WILLIAMSTOWN
PROJECT NUMBER: BRS 0204 (4)

FILE NAME: 83e111/structures/s83e111tc.dgn
PROJECT LEADER: M. EVANS-MONGEON
DESIGNED BY: M. EVANS-MONGEON
TRAFFIC SIGN SUMMARY SHEET 1

PLOT DATE: 07-APR-2008
DRAWN BY: M. EVANS-MONG
CHECKED BY: U. STANLEY
SHEET 40 OF 108