STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (In) FOUND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
VT 14 STA. 336+88 RT	BROOKFIELD →	1	72	12	6.0						2						38.	X														X	DI-1 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-123
	← SOUTH BARRE	1	72	12	6.0																												DI-1 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-123
	NORTH	1	24	12	2.0																												M3-1 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-136B
	SOUTH	1	24	12	2.0																												M3-3 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-136B
	VERMONT 14	2	24	24	8.0																												M1-6 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-136B
	←	1	21	15	2.19																												M6-1 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-136B
	→	1	21	15	2.19																												M6-1 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-136B
VT 14 STA 337+89 LT	↑ E BROOKFIELD 8	1	72	12	6.0						2						36.	X														X	DI-1 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-123
	SOUTH	1	24	12	2.0																												M3-3 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-136B
	TO	1	24	12	2.0																												M4-5 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-135
	WEST	1	24	12	2.0																												M3-4 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-136B
	VERMONT 14	1	24	24	4.0																												M1-6 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-136B
	INTERSTATE 89	1	24	24	4.0																												M1-1 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-135
	VERMONT 64	1	24	24	4.0																												M1-6 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-136B
	↑	1	21	15	2.19																												M6-3 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-136B
	→	1	21	15	2.19																												M6-1R SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-135
	→	1	21	15	2.19																												M6-1 SALVAGE AND RELOCATE SIGN FOR DETOUR NEW SIGN, AND REMOVE OLD SIGN		E-136B
					58.95							FT	FT	FT	FT	FT	FT	EA	EA	LB	LB	LB		LB	LB	LB	LB					4. EA			
					SF	SF	EA.	SF				FT			FT					LB			EA.	LB				EA.	EA.	LB					
					SUBTOTALS(2) 58.95							0.			74.			4.													4.				
					SUBTOTALS(1) 57.82							64.			102.			2.													2.				
					ROUNDING 3.23																														
					TOTALS 120.00							64.			176.			6.													6.				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WILLIAMSTOWN
PROJECT NUMBER: BRS 0204 (4)

FILE NAME: 83ell/structures/sellltc.dgn
PROJECT LEADER: M. EVANS-MONGEON
DESIGNED BY: M. EVANS-MONGEON
TRAFFIC SIGN SUMMARY SHEET 2

PLOT DATE: 07-APR-2008
DRAWN BY: M. EVANS-MONG
CHECKED BY: U. STANLEY
SHEET 41 OF 108