PROJECT LENGTHS AND ITEM QUANTITIES

ITEM DESCRIPTION	LENGTH	WIDTH	OVERLAY DEPTH	24" STOP BARS	LETTER IN WORD MARKINGS	GRAVEL SHOULDERS	GRAVEL SHOULDERS	EMULSIFIED ASPHALT	BITUMINOUS CONCRETE PAVEMENT	CHANGE ELEV. OF CB, DI, OR MH	ALL PURPOSE EXC. RENTAL, TYPE I	POWER BROOM RENTAL,	UNIFORMED TRAFFIC OFFICERS	FLAGPERSONS	MOBILIZATION	TEMPORARY PAVEMENT MARKING- White	TEMPORARY PAVEMENT MARKING- Yellow	
ITEM NUMBER				646.20	646.23	402.10	402.11	404.65	406.25	604.40	608.25	608.30	630.10	630.15	635.10	646.35	646.36	REMARKS
UNIT	FEET	FT	INCH	LF	EA	CY	TON	CNT	TON	EA	HR	HR	HR	HR	LS	LF		
LOCATION																		
Essex MM 1.101 ~ MM 1.18 *	417	24	1½"					3	93									1½" WEARING COURSE
Essex MM 1.101 ~ MM 1.18		8	1½"			63	104											8' GRAVEL SHOULDER
Essex MM 1.101 ~ Colchester MM 2.165	(24188)	24							999									218 TON/MI. LEVEL
Essex MM 1.18 ~ * MM 3.517	12339	24	1½"					83	2743									1½" WEARING COURSE
Colchester MM 0.00 ~ MM 2.13 *	11246	24	1½"					76	2500									1½" WEARING COURSE
Colchester MM 2.13 - MM 2.20 *	370	27	1½"					3	93									1½" WEARING COURSE TAPER
Colchester MM 2.20 - MM 2.431 *	1220	30	1½"					11	339									1½" WEARING COURSE
Colchester MM 2.165 ~ MM 2.431	(1404)	30							73									273 TON/MI. LEVEL
PROJ. ESTIMATE																		
DRIVES & APPROACH						1510	2495		325									
PROJECT				15	25			176		1	1	40	187	187	1	51184	81555	FOR ITEM 646.23
ROUND				-	-	27	1	4	12				3	3		16	45	SEE SHT. 9 OF 12
TOTAL	25592			15	25	1600	2600	180	7200	1	1	40	190	190	1	51200	81600	

PROJECT Essex - Colchester NUMBER HMA 2450 SHEET 4 OF 12