PROJECT MIDDLEBURY-BRISTOL ROUTE VT 116 PROJECT NUMBER HMA 2518

TEMPORARY 4" REFLECTORIZED YELLOW LINE

MILE	MILE	LT	RT				
				107075 Lf Needed for 1 Application			
				from 1st Sheet 4" ℄			
	Assume 75% of ℄ Lost on						
	Leveling						
		107075 1 x 175% = 187381					

Note.
ALTHOUGH NOT SHOWN ON
THIS SHEET, THE ℄ SHALL BE
BROKEN AT ALL TOWN HIGHWAY
INTERSECTIONS AS SHOWN ON
THE PLAN DETAIL SHEET

TEMPORARY 4" REFLECTORIZED WHITE LINE

Bristol - Lt Turn Lane							
5.95	6.025	RT of ℄	Solid				396
Edge Lines Proj Length To Be painted 62,761 Lf							
	Edge Lines - 62,761 x 2 = 125,522 Lf						
				Turnlane + 396			
				125,918			
				Rounding -82			
			4" White est.	126,000			

Note Paint 2 ea Lt Arrow with ONLY
in Lt Turn Lane Bristol 5.95-6.025 Area - See STANDARD E-50

MIDDLEBURY-BRISTOL
HMA 2518 sheet 8A of 11
HMA 2465