

TEMPORARY 4" REFLECTORIZED YELLOW LINE

MILE	MILE	LT	RT		
1.315	1.35	SOLID	SOLID		370
1.35	1.46	SOLID	DASH		726
1.46	1.72	DASH	DASH		343
1.72	1.87	DASH	SOLID		990
1.87	1.89	SOLID	SOLID		211
1.89	2.03	SOLID	DASH		924
2.03	2.36	DASH	DASH		436
2.36	2.44	DASH	SOLID		528
2.44	2.63	SOLID	SOLID		2,006
2.63	2.71	SOLID	DASH	ALTHOUGH NOT SHOWN ON THIS SHEET THE C	528
2.71	3.03	DASH	DASH	SHALL BE BROKEN AT ALL TOWN HIGHWAY INTERSECTIONS	422
3.03	3.11	DASH	SOLID	AS SHOWN ON THE PLAN	528
3.11	3.13	SOLID	SOLID	DETAIL SHEET	211
3.13	3.21	SOLID	DASH		528
3.21	3.700	DASH	DASH		647
					9398
ASSUME 50% LOST DURING LEVELING					
$9398 \times 150\% = 14097$ Round to 14,100					
TEMPORARY 4" REFLECTORIZED WHITE LINE					
EDGE LINES BOTH SIDES ENTIRE PROJ.					
PROJ. LENGTH 2.385 mi. $\times 5280 = 12,593$					
$12,593 \times 2 = 25,186$					
Round 14					
4" White Est 25,200 LF.					
AT M/M 1.365 INSTALL 1 EA DURABLE R-R SYMBOL - SEE STANDARD					
ITEM 646.67 DURABLE RR MARKING 1 EA					
BERKSHIRE					
F 034-1(15)S					
Sheet 8 of 11					