

TEMPORARY 4" REFLECTORIZED YELLOW LINE

MILE	MILE	LT	RT	QUANTITY LT.	QUANTITY E	QUANTITY RT.	TOTAL
MT. HOLLY							
1.626	1.82	SOLID	SOLID	1024		1024	2048
1.82	2.27	DASH	SOLID	594		2376	2970
2.27	2.68	SOLID	SOLID	2165		2165	4330
2.68	2.78	SOLID	DASH	528		132	660
2.78	2.80	DASH	DASH		26		26
2.80	2.90	DASH	SOLID	132		528	660
2.90	3.02	SOLID	SOLID	634		634	1268
3.02	3.20	SOLID	DASH	950		238	1188
3.20	3.35	DASH	DASH		198		198
3.35	3.46	DASH	SOLID	145		581	726
3.46	4.14	DASH	DASH		898		898
4.14	4.21	DASH	SOLID	92		370	462
4.21	4.24	SOLID	SOLID	158		158	316
4.24	4.33	SOLID	DASH	475		119	594
4.33	5.00	DASH	DASH		884		884
5.00	5.20	DASH	SOLID	264		1056	1320
5.20	5.78	SOLID	SOLID	3062		3062	6124
5.78	5.93	SOLID	DASH	792		198	990
5.93	6.08	DASH	DASH		198		198
6.08	6.10	DASH	SOLID	26		106	132
6.10	7.68374	SOLID	SOLID	8358		8358	16716
WALLINGFORD							
0.00	0.45	SOLID	SOLID	2376		2376	4752
				21775	2204	23481	47460
14 SIDE ROAD OPENINGS @ 40' EACH							
14 x 40 x 2 = 1120							
- 1120							
46340							
ASSUME 50% LOST DURING LEVELING							
46340 x .5 = 23170							
+ 23170							
SUB-TOTAL 69510							
ROUND 40							
TOTAL 69550							
SHEET 11A OF 13							