

QUANTITY SHEET



SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
				ROADWAY	EROSION CONTROL	UTILITIES (NO FED/ST PART)	BRIDGE	FULL C.E. ITEMS	DESEL EMISSIONS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
				1						1		LS	MOBILIZATION/DEMobilIZATION	635.11	--			
				1						1		LS	TRAFFIC CONTROL	641.10	--			
				240						240		M	DURABLE 100 MM WHITE LINE	646.400	4.5			
				160						160		M	DURABLE 100 MM YELLOW LINE	646.410	2.6			
				6						6		M	DURABLE 600 MM STOP BAR	646.480	2			
				4						4		EACH	DURABLE LETTER OR SYMBOL	646.490	--			
				830						830		M	TEMPORARY 100 MM YELLOW LINE	646.610	EST.			
				9						9		M	TEMPORARY 600 MM STOP BAR	646.680	EST.			
				90						90		SM	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	EST.			
							310			310		SM	GEOTEXTILE UNDER STONE FILL	649.31	3			
					90					90		SM	GEOTEXTILE FOR SILT FENCE	649.51	EST.			
					10					10		KG	SEED	651.15	EST.			
					50					50		KG	FERTILIZER	651.18	EST.			
					1					1		T	AGRICULTURAL LIMESTONE	651.20	EST.			
					1					1		T	HAYMULCH	651.25	EST.			
					10					10		CM	TOPSOIL	651.35	EST.			
							40			40		SM	GRUBBING MATERIAL	651.40	EST.			
										1		LS	EPSC PLAN	652.10	--			
					60					60		HR	MONITORING EPSC PLAN	652.20	EST.			
					1					1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30	--			
					300					300		SM	TEMPORARY EROSION MATTING	653.20	EST.			
													BEGN OPTION BB					
					10					10		CM	TEMPORARY STONE CHECK DAM, TYPE II	653.26	EST.			
					6					6		EACH	PREFABRICATED CHECK DAM	653.30	EST.			
													END OPTION BB					
					20					20		CM	VEHICLE TRACKING PAD	653.35	EST.			
													BEGN OPTION CC					
					4					4		EACH	INLET PROTECTION DEVICE, TYPE I	653.40	--			
					4					4		EACH	INLET PROTECTION DEVICE, TYPE II	653.41	--			
													END OPTION CC					
					25					25		M	BARRIER FENCE	653.50	EST.			
					162					162		M	PROJECT DEMARCATION FENCE	653.55	EST.			
					4					4		SM	TRAFFIC SIGNS, TYPE A	675.20	.17			
					40					40		M	FLANGED CHANNEL SIGN POST	675.301	4			
					10					10		EACH	REMOVING SIGNS	675.50	--			
						110				110		M	ELECTRICAL CONDUIT SLEEVE (100 MM) (PVC)	678.30	--			
					40					40		CM	SPECIAL PROVISION (STONE FILL, CULVERT LNING)	900.608	10.2			
							1			1		LS	SPECIAL PROVISION (TEMPORARY RELOCATION OF STREAM)	900.645	--			
									1	1		LU	SPECIAL PROVISION (EMISSION CONTROL DEVICE, CRANE) (N.A.B.I.)	900.650	--			
									1	1		LU	SPECIAL PROVISION (EMISSION CONTROL DEVICE, DUMP TRUCK) (N.A.B.I.)	900.650	--			
									1	1		LU	SPECIAL PROVISION (EMISSION CONTROL DEVICE, EXCAVATOR) (N.A.B.I.)	900.650	--			

PROJECT NAME: **POWNAI**
PROJECT NUMBER: **STP RS 0107(8)**
FILE NAME: VAOT_quant_sc028.xls PLOT DATE: 05/16/2007
PROJECT MANAGER: W. SYMONDS DRAWN BY: R. PELLETT
DESIGNED BY: G. SHANGRAW CHECKED BY: T. SUMNER
QUANTITY SHEET #2 SHEET 9 OF 65