QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

NON GOV'T PARTIC.	TRAINING	WETLAND MITIGATION	EROSION CONTROL	#79 BRIDGE	#80 BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
						60	60	LF	18 INCH CAAP .060	601.0215	6
						60	60	LF	18 INCH PCCSP .064	601.0415	6
						60	60	LF	18 INCH RCP CLASS III	601.0815	6
						60	60	LF	18 INCH CPEP (SL)	601.2615	6
						190	190	LF	24 INCH CAAP .060	601.0225	6
						190	190	LF	24 INCH PCCSP .064	601.0425	6
						190	190	LF	24 INCH RCP CLASS III	601.0825	6
						190	190	LF	24 INCH CPEP (SL)	601.2620	6
						130	130	LF	24 INCH CAAP .060	601.0225	2
						130	130	LF	24 INCH PCCSP .064	601.0425	2
						130	130	LF	24 INCH RCP CLASS IV	601.0826	2
						130	130	LF	24 INCH CPEP (SL)	601.2620	2
						70	70	LF	24 INCH CAAP .060	601.0225	2
						70	70	LF	24 INCH PCCSP .064	601.0425	2
						70	70	LF	24 INCH CPEP (SL)	601.2620	2
						12	12	EA	12 INCH CSP ELBOW .064 (2 2/3 X 1/2)	601.5005	
						12	12	EA	12 INCH CAAP ELBOW .060 (2 2/3 X 1/2)	601.5205	
						12	12	EA	12 INCH CPEP ELBOW (SL)	601.5804	
						1	1	EA	18 INCH CSPES .064 (2 2/3 X 1/2)	601.6015	
						1	1	EA	18 INCH CAAPES .060 (2 2/3 X 1/2)	601.6215	
						1	1	EA	18 INCH RCPES CLASS III	601.6815	
						1	1	EA	18 INCH CPEPES	601.7015	
						2	2	EA	24 INCH CSPES .064 (2 2/3 X 1/2)	601.6025	
						2	2	EA	24 INCH CAAPES .060 (2 2/3 X 1/2)	601.6225	
						2	2	EA	24 INCH RCPES CLASS III	601.6825	
						2	2	EA	24 INCH CPEPES	601.7020	
						1	1	EA	24 INCH CSPES .064(2 2/3 X 1/2)	601.6025	
						1	1	EA	24 INCH CAAPES .060(2 2/3 X 1/2)	601.6225	
						1	1	EA	24 INCH CPEPES	601.7020	
									** END OPTION PIPES **		
						15	15	CY	CEMENT RUBBLE MASONRY	602.15	1.8
						6	6	EA	PRECAST REINFORCED CONCRETE CURB DROP INLET W/CAST IRON GRATE	604.30	
						710	710	LF	6" UNDERDRAIN	605.10	2
						4	4	EA	UNDERDRAIN FLUSHING BASINS	605.95	
						50	50	HR	ROADWAY PATROL MAINTENANCE	607.10	EST.
						1	1	HR	BULLDOZER RENTAL TYPE I (NOT A BID ITEM)	608.10	
						1	1	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I (NABI)	608.25	
						1	1	HR	TRUCK RENTAL (NOT A BID ITEM)	608.37	
						1	1	HR	LOADER RENTAL TYPE I (NOT A BID ITEM)	608.40	
						250	250	MGAL	DUST CONTROL WITH WATER	609.10	5
						2	2	TON	DUST & ICE CONTROL WITH CALCIUM CHLORIDE	609.15	.25
			4.9			12.1	17	CY	STONE FILL TYPE I	613.10	
				200	1000	275	1,475	CY	STONE FILL TYPE II	613.11	22.3
						1,780	1,780	CY	STONE FILL TYPE III	613.12	7.6
				1,325		750	2,075	CY	STONE FILL TYPE IV	613.13	18
						1,450	1,450	LF	TREATED TIMBER CURB	616.35	25
						2	2	EA	RELOCATE MAIL BOX SINGLE SUPPORT	617.10	
						4	4	EA	BOUNDARY MARKERS	619.10	
						20	20	EA	YIELDING MARKER POSTS	619.17	
						6	6	EA	REMOVING AND RESETTING PROPERTY MARKERS	619.20	
						300	300	LF	REMOVING AND RESETTING FENCE (MOD)	620.50	40
						110	110	LF	BARBED WIRE FENCE (4 STRAND)	620.60	
						2,200	2,200	LF	SNOW FENCE (MODIFIED)	620.70	30

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS		PAVEMENT WIDTHS			EQUATIONS		FEET	MILES	REMARKS
FROM	TO				+	−			
TOTALS									

PROJECT NAME WALLINGFORD
PROJECT NUMBER BRS – 0137 (13)

D:\CIVIL\WALLY\91120-06.DWG (1=1)