



PAINT ALL AROUND (UN)
SEE SHT. N1
35'-6"

GIRDER ~ MK. G3B

PAINT LIGHT RUST PREVENTIVE
COAT OF PRIMER (FS),
EDGES & SHADED AREA (NS)

SHOP DRAWING REVIEW
IDENTIFY FOR GENERAL COMPLIANCE WITH
CONTRACT REQUIREMENTS, AND RESPONSIBILITY
FOR THE DESIGN OF THE WORK SHALL BE
MAINTAINED BY THE CONTRACTOR.
DATE: MAR 22 1996
BY: [Signature]

SHOP NOTE
HOLES: 1/8" Ø (UN)
BOLTS: AS NOTED
PAINT: AS NOTED, SEE DWG. N1.
FOR GENERAL SHOP NOTES, SEE DWG. N1.
FOR WEB CAMBER DIAGRAM, SEE DWG. WC1.

BILL OF MATERIAL						
NO.	MARK	DESCRIPTION	LENGTH	REMARKS	ITEM	QTY
ONE	G3B	GIRDER				29000
1	a	PL 62 x 3/8	65	6 1/8 (T)	2	4
1	b	PL 62 x 3/8	42	11 1/4 (T)	2	5
1	c	PL 16 x 1 1/2	72	11 1/8 (T)	2	13
1	d	PL 16 x 1 1/2	35	6 (T)	2	14
1	f	PL 16 x 1 1/2	72	8 1/2 (T)	2	13
1	g	PL 16 x 1 1/2	35	6 (T)	2	14
2	x1k	PL 58 x 3/8	1	1 (T)	3	6
2	x1m	PL 16 x 3/8	2	1 (T)	3	4
4	x1n	BAR 7 x 3/4	2	1 (T)	3	2
2	x1b	BAR 7 1/2 x 7/8	5	2	3	12
10	x1f	BAR 7 1/2 x 7/8	5	2	3	14

NO.	REVISION	DATE
1	CHANGED "MILL" TO "GRIND"	2-21-96

HIGH STEEL STRUCTURES, INC. 1770 Hempstead Road Lancaster, PA 17603-0008 Phone 717-299-5211
A Division of High Production, Inc.

GIRDER	G3B
U.S. ROUTE 7 OVER OTTER CREEK	
BRIDGE NO. 79	
TOWN OF WALLINGFORD, COUNTY OF RUTLAND	
STATE OF VERMONT	
AGENCY OF TRANSPORTATION	
STATE CONTRACT OR REF. NO.	PROJECT NO. BRS-0137(13)
CONTRACTOR	J. A. McDONALD, INC.
IN CHARGE:	abs MADE PFP 2-3 CHG'D BY LJD DATE 2-3-96
CONTRACT NUMBER:	VT-95367 DRAWING NUMBER: 19 OF 24