



BILL OF MATERIAL						
NO.	MARK	DESCRIPTION	LENGTH	REMARKS	ITEM	QTY
ONE	G4B	GIRDER				29020
1	a	PL 62 x 3/8	65 6 1/2	(T)		2 4
1	b	PL 62 x 3/8	42 11 1/2	(T)		2 5
1	c	PL 16 x 1 1/2	72 11 1/2	(T)		2 15
1	d	PL 16 x 1 1/2	35 6	(T)		2 14
1	f	PL 16 x 1 1/2	72 9	(T)		2 15
1	g	PL 16 x 1 1/2	35 6	(T)		2 14
2	x1k	PL 58 x 3/8	1 1	(T)		3 6
2	x1m	PL 16 x 3/8	2 1	(T)		3 4
4	x1n	BAR 7 x 3/4	2 1	(T)		3 2
2	x1b	BAR 7 1/2 x 3/4	5 2			3 12
10	x1f	BAR 7 1/2 x 1/2	5 2			3 14

GIRDER ~ MK. G4B

SHOP DRAWING REVIEW
 GENERAL: FOR GENERAL COMPLIANCE WITH
 DRAWING OR CONTRACTOR'S SHOP DRAWINGS
 CONTRACTOR'S RESPONSIBILITY TO VERIFY
 ALL DIMENSIONS FOR CORRECTNESS
 IN ACCORDANCE WITH CONTRACT
 CHECKED BY: [Signature]
 APPROVED BY: [Signature]
 DATE: MAR 22 1996

PAINT LIGHT RUST PREVENTIVE
 COAT OF PRIMER (FS),
 EDGES & SHADED AREA (NS)

SHOP NOTE
 HOLES: 1/8" (UN)
 BOLTS: AS NOTED
 PAINT: AS NOTED, SEE DWG. N1
 FOR GENERAL SHOP NOTES, SEE DWG. N1
 FOR WEB CAMBER DIAGRAM, SEE DWG. WC1.

NO.	REVISION	DATE
1	CHANGED "MILL" TO "GRIND"	2-21-96

HIGH STEEL STRUCTURES, INC. 1770 Hempstead Road
 Concord, MA 01702-0008
 Phone: 717/299-5211
 A Division of High Industries, Inc.

GIRDER G4B

U.S. ROUTE 7 OVER OTTER CREEK
 BRIDGE NO. 79
 TOWN OF WALLINGSFORD, COUNTY OF RUTLAND
 STATE OF VERMONT
 AGENCY OF TRANSPORTATION

STATE CONTRACT OR REF. NO. PROJECT NO. BRS-0137(13)
 CONTRACTOR: J. A. McDONALD, INC.
 IN CHARGE: abs MAKE PFP 2-3 CH'D BY LD DATE: 2-3-96
 CONTRACT NUMBER: VT-95367 DRAWING NUMBER: 20 OF 24