

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES														TOTALS			DESCRIPTIONS		DETAILED SUMMARY OF QUANTITIES					
APPR SLAB NO.	ABUT NO. 1	PIER NO. 1	DECK	PIER NO. 2	ABUT NO. 2	APPR SLAB NO.			DETOUR	UTILITIES	TRAINING	FULL E&C ITEMS	EROSION CONTROL	ROADWAY	BRIDGE QUANTITY	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS
														10			10		HR	LOADER RENTAL, TYPE I	608.40			
													173				173		MGAL	DUST CONTROL WITH WATER (MOD.)	609.10			
														1			1		TON	DUST & ICE CONTROL WITH CALCIUM CHLORIDE	609.15			
													25				25		CY	STONE FILL, TYPE I	613.10			
													20				20		CY	STONE FILL, TYPE I (MOD- CONSTRUCTION ENTRANCE)	613.10			
														330			330		CY	STONE FILL, TYPE II	613.11			
	440	140		140	150											870		CY	STONE FILL, TYPE IV	613.13				
																180		LF	CAST-IN-PLACE CEMENT CONCRETE CURB, TYPE B	616.28				
																2050		LF	SNOW FENCE (MOD - PDF)	620.70				
																40		LF	SNOW FENCE (MOD -TREE PROTECTION)	620.70				
																750		LF	HEAVY DUTY STEEL BEAM GUARD RAIL (GALVANIZED)	621.21				
																3		EACH	MANUFACTURED TERMINAL SECTION (FLARED)	621.505				
																1		EACH	MANUFACTURED TERMINAL SECTION (TANGENT)	621.505				
																4		EACH	GUARD RAIL APPR. SECTION.NETC 2 RAIL	621.72				
																733		LF	REMOVAL AND DISP OF GUARD RAIL	621.80				
									0.2							0.2		MFBM	INSULATION BOARD	622.10				
									70							70		LF	DUCTILE IRON PIPE, CEM LINED (CL 52, 16")	629.24				
									2							2		EACH	GATE VALVE (16")	629.26				
									225							225		LF	PLASTIC WATER PIPE, RIGID (12" - CLASS 200)	629.33				
									2							2		EACH	TAPPING SLEEVE & VALVE WITH VALVE BOX (12")	629.35				
									1							1		LS	TRANSFER TO NEW SYSTEM-WATER SYSTEM	629.42				
									250							250		LF	PIPE INSULATION	629.44				
									200							200		TON	CRUSHED STONE BEDDING	629.54				
									1							1		LS	WATER MAIN ON BRIDGE (TEMPORARY) (12")	629.60				
									1							1		LS	WATER MAIN ON BRIDGE (PERMANENT) (18")	629.60				
																250		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
																250		HR	FLAGGERS	630.15				
																1		LS	FIELD OFFICE-ENGINEERS	631.10				
																1		LS	TESTING EQUIPMENT - CONCRETE	631.16				
																1		LS	TESTING EQUIPMENT - BITUMINOUS	631.17				
																1		LU	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.25				
										520						520		HR	EMPLOYEE TRAINEESHIP	634.10				
																1		LS	MOBILIZATION/ DEMOBILIZATION	635.11				
																1		LS	TRAFFIC CONTROL	641.10				
																2700		LF	DURABLE 4" WHITE LINE	646.40				
																2700		LF	DURABLE 4" YELLOW LINE	646.41				
																55		EACH	LINE STRIPING TARGETS	646.76				
	504	66		66	197											508	833	1339	SY	GEOTEXTILE UNDER STONE FILL	649.31			
																1100		1100	SY	GEOTEXTILE FOR SILT FENCE	649.51			
																70		LB	SEED	651.15				
																20		LB	SEED-WINTER RYE	651.17				

PROJECT NAME: **WOODFORD**
 PROJECT NUMBER: **BHF 010-1(29)**
 FILE NAME: /84e039/se039qs.xls PLOT DATE: 8/2/2005
 PROJECT LEADER: A. PORTALUPI DRAWN BY: G. SHANGRAW
 DESIGNED BY: EVANS-MONGEON CHECKED BY: M.E.M.
 QUANTITY SHEET #2 SHEET 7 OF 106