QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

						UTILITY	NON-GOVT. PARTIC.	TRAINING	EROSION CONTROL	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
										10		10	EA	BEARING DEVICE ASSEMBLY	531.10	–
											152	152	LF	18" CPEP (SL)	601.2615	0
											1	1	EA	18" CPEPES	601.7015	0
														********** BEGIN OPTION PIPES **********		
											84	84	LF	18" RCP CLASS III	601.0815	0
											84	84	LF	18" CPEP (SL)	601.2615	0
											68	68	LF	18" CAAP .060 (2-2/3 X 1/2)	601.0215	0
											68	68	LF	18" PCCSP .064 (2-2/3 X 1/2)	601.0415	0
											68	68	LF	18" CPEP (SL)	601.2615	0
											1	1	EA	18" RCPES CLASS III	601.6815	0
											1	1	EA	18" CPEPES	601.7015	0
											1	1	EA	18" CSPES .064 (2-2/3 X 1/2)	601.6015	0
											1	1	EA	18" CAAPES .060 (2-2/3 X 1/2)	601.6215	0
											1	1	EA	18" CPEPES	601.7015	0
														********** END OPTION PIPES **********		
							55					55	LF	RELAYING PIPE CULVERTS (MOD.)	601.99	EST.
											100	100	LF	6" UNDERDRAIN	605.10	EST.
											100	100	LF	6" UNDERDRAIN CARRIER PIPE	605.20	EST.
											1	1	EA	UNDERDRAIN FLUSHING BASINS	605.95	EST.
											1	1	HR	BULLDOZER RENTAL, TYPE I (NOT A BID ITEM)	608.10	EST.
											1	1	HR	POWER GRADER RENTAL (NOT A BID ITEM)	608.15	EST.
											1	1	HR	ALL PURP. EXCAV. RENT. TYPE I (NOT A BID ITEM)	608.25	EST.
											1	1	HR	TRUCK RENTAL (NOT A BID ITEM)	608.37	EST.
											200	200	MGAL	DUST CONTROL WITH WATER	609.10	EST.
											2.0	2.0	TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15	EST.
										20		20	CY	STONE FILL, TYPE I	613.10	EST.
										10		10	CY	STONE FILL, TYPE II	613.11	4
											2460	2460	CY	STONE FILL, TYPE IV	613.13	–
											15	15	EA	BOUNDARY MARKERS	619.10	EST.
											7	7	EA	YIELDING MARKER POSTS	619.17	0
											20	20	LF	GATE FOR CHAIN-LINK FENCE, 4 FEET (MOD.)	620.15	0
											270	270	LF	REMOVAL OF EXISTING FENCE (1-STRAND)	620.55	EST.
											200	200	LF	BARBED WIRE FENCE (4-STRAND)	620.60	EST.
											775	775	LF	STEEL BEAM GUARDRAIL	621.20	12.5
											5	5	EA	MODIFIED ECCENTRIC LOADER TERMINAL	621.52	0
											1	1	EA	ANCHOR FOR STEEL BEAM GUARDRAIL	621.60	0
											4	4	EA	GUARDRAIL APPROACH SECTION, TYPE I	621.70	0
											370	370	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	3
											4	4	EA	REMOVAL AND DISPOSAL OF GUIDE POSTS	621.81	0

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME BRAINTREE
PROJECT NUMBER BRS 0187(6)

902820TV.DWG Sht #6 (1=1)