QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

						UTILITY	NON-GOVT. PARTIC.	TRAINING	EROSION CONTROL	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
											100	100	LF	TEMPORARY TRAFFIC BARRIER	621.90	EST.
											230	230	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
											600	600	HR	FLAGGERS	630.15	EST.
											1	1	LS	FIELD OFFICE–ENGINEERS	631.10	–
										1		1	LS	TESTING EQUIPMENT – CONCRETE	631.16	–
										0.1	0.9	1	LS	TESTING EQUIPMENT – BITUMINOUS	631.17	–
											1	1	LS	FIELD OFFICE TELEPHONE (NOT A BID ITEM)	631.25	–
								540				540	HR	EMPLOYEE TRAINEESHIP	634.10	–
											1	1	LS	MOBILIZATION	635.10	–
											3000	3000	LF	DURABLE 4" WHITE LINE	646.40	81
											2850	2850	LF	DURABLE 4" YELLOW LINE	646.41	30
											20	20	LF	DURABLE 24" STOP BAR	646.46	0
											750	750	LF	TEMPORARY 4" WHITE LINE	646.60	EST
											2850	2850	LF	TEMPORARY 4" YELLOW LINE	646.61	30
											115	115	EA	LINE STRIPING TARGETS	646.73	4
									40	800		840	SY	GEOTEXTILE UNDER STONE FILL	649.31	10
									700			700	SY	GEOTEXTILE FOR SILT FENCE	649.51	EST.
									180			180	SY	GEOTEXTILE FOR FILTER CURTAIN	649.61	EST.
									170			170	LB	SEED	651.15	EST.
									7			7	LB	SEED – WINTER RYE	651.17	EST.
									1375			1375	LB	FERTILIZER	651.18	EST.
									6			6	TON	AGRICULTURAL LIMESTONE	651.20	EST.
									6			6	TON	HAY MULCH	651.25	EST.
									350			350	EA	HAY BALES FOR EROSION CONTROL	651.26	EST.
											150	150	CY	TOPSOIL	651.35	EST.
										620		620	SY	GRUBBING MATERIAL	651.40	–
									950			950	SY	EROSION MATTING	654.10	EST.
											68	68	SF	TRAFFIC SIGNS, TYPE A	675.20	0.4
											600	600	LB	FLANGED CHANNEL SIGN POSTS	675.30	8
											17	17	EA	REMOVING SIGNS	675.50	0
														ALTERNATE 'A'		
											3600	3600	CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	34
														ALTERNATE 'B'		
											3600	3600	CY	SUBBASE OF CRUSHED GRAVEL (COARSE GRADED)	301.25	34

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		TEMPORARY EROSION CONTROL
35	CY	TRENCH EXCAVATION OF EARTH
175	CY	SUBBASE
20	CY	STONE FILL, TYPE I
155	SY	GEOTEXTILE FOR SILT FENCE
7	LB	SEED – WINTER RYE
1	TON	HAY MULCH
100	EA	HAY BALES FOR EROSION CONTROL
100	SY	EROSION MATTING

PROJECT NAME BRAINTREE
PROJECT NUMBER BRS 0187(6)