

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
FULL C.E. ITEMS			BRIDGE NO. 1	UTIL SEWER (NO FED./ST. PARTICIP.)	UTIL WATER (NO FED./ST. PARTICIP.)	EROSION CONTROL	TRAINING	ROADWAY (NO FEDERAL PARTICIP.)	ROADWAY	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
			423							423		SY	SHEET MEMBRANE WATERPROOFING (MOD. - TORCH APPLIED)	519.20	0.8			
			80							80		LF	METAL HAND RAILING (MOD. - TEMPORARY PEDESTRIAN RAILING)	525.15	-			
			155							155		LF	BRIDGE RAILING - ALUMNUMPEDESTRIAN (MOD. - ANODIZED BLACK)	525.23	0.8			
			1							1		LS	MAINTENANCE OF TRAFFIC FOR BRIDGE PROJECTS (MOD.)	527.10	-			
			1							1		LS	TWO-WAY TEMPORARY BRIDGE (1500 SF - EST.) (MOD. - 22' WIDE)	528.11	-			
			1							1		EACH	REMOVAL OF STRUCTURE (2000 SF - EST.)	529.15	-			
			18							18		EACH	BEARING DEVICE ASSEMBLY (FABRIC)	531.10	-			
									4	4		LF	12" PCCSP .064 (2-2/3 X 1/2)	601.0405	-			
													BEGIN OPTION AA					
									36	36		LF	18" CAAP .060 (2-2/3 X 1/2)	601.0215	-			
									36	36		LF	18" PCCSP .064 (2-2/3 X 1/2)	601.0415	-			
													END OPTION AA					
													BEGIN OPTION BB					
									90	90		LF	24" CAAP .060 (2-2/3 X 1/2)	601.0225	-			
									90	90		LF	24" PCCSP .064 (2-2/3 X 1/2)	601.0425	-			
													END OPTION BB					
									4	4		LF	18" RCP CLASS III	601.0815	-			
													BEGIN OPTION CC					
									146	146		LF	18" RCP CLASS III	601.0815	-			
									146	146		LF	18" CPEP(SL)	601.2615	-			
													END OPTION CC					
													BEGIN OPTION DD					
									454	454		LF	24" RCP CLASS III	601.0825	-			
									454	454		LF	24" CPEP(SL)	601.2620	-			
													END OPTION DD					
									1	1		EACH	CONCRETE CATCH BASIN WITH CAST IRON GRATE	604.10	-			
				2						2		EACH	SANITARY SEWER MANHOLE (MOD. - SIPHON CHAMBER)	604.22	-			
									10	10		EACH	CAST IRON GRATE WITH FRAME, TYPE D	604.47	-			
									800	800		LF	6" UNDERDRAIN (MOD.)	605.10	31			
									95	95		LF	6" UNDERDRAIN CARRIER PIPE (MOD.)	605.20	-			
									8	8		EACH	UNDERDRAIN FLUSHING BASINS (MOD.)	605.95	-			
						5			25	30		HR	BULLDOZER RENTAL, TYPE I	608.10	EST			
									25	25		HR	POWER GRADER RENTAL	608.15	EST			
						5			45	50		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST			
						5			90	95		HR	TRUCK RENTAL	608.37	EST			
									100	100		MGAL	DUST CONTROL WITH WATER	609.10	EST			
									4	4		TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15	EST			
						20			20	20		CY	STONE FILL, TYPE I (MOD. - INLET PROTECTION)	613.10	EST			
						50			50	50		CY	STONE FILL, TYPE I	613.10	-			
						10			10	10		CY	STONE FILL, TYPE I (MOD. - CHECK DAM)	613.10	EST			
						70			70	70		CY	STONE FILL, TYPE I (MOD. - CONSTRUCTION ENTRANCE)	613.10	EST			

PROJECT NAME: JOHNSON  
PROJECT NUMBER: BRF 030-2(17)S

FILE NAME: 06-0246\_QSS.xls PLOT DATE: 02/12/2007  
PROJECT MANAGER: JPB DRAWN BY: MWS  
DESIGNED BY: JAW CHECKED BY: PTS  
QUANTITY SHEET #2 SHEET 5 OF 85