STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 2.30	SQUARE STEEL (in) 2.0 lb/ft 2.65	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
STA 101+66 LT		1	30"	30"	6.25						1			14' X		X		X															W11-8		
STA 101+76 RT	SPEED LIMIT 25	1	24"	30"	5.00						1			14' X		X		X															R2-1		E-142
STA 102+63 RT	T.I.S.	1	72"	16"			1																2	1@ 11' X 1@ 11.25	22.25 x 7.6 = 169.1 LBS								PLACE SALVAGED SIGNS ON TWO 3-INCH DIA. TUBULAR STEEL POSTS NON FEDERAL PARTICIPATION		E-125
	T.I.S.	1	72"	16"			1																												E-125
	T.I.S.	1	72"	16"			1																												E-125
STA 102+81 RT	BRIDGE 37 VT 15	1	6"	8"	0.33						1			8' X		X		X															VD-701		E-134
STA 103+84 LT		1	30"	30"	6.25						1			16' X		X		X															W11-9		
	NEXT 3,000 FT	1	24"	18"	3.00																												W16-4		
STA 103+89 LT	BRIDGE 37 VT 15	1	6"	8"	0.33						1			8' X		X		X															VD-701		E-134
STA 104+45 RT		1	12"	12"	1.00						1			16' X		X		X															R8-3A		E-143
	1 A.M. - 6 A.M. NOV. 1 - APR. 15	1	12"	6"	0.50																												R8-3E	19	
	BEGIN	1	12"	8"	0.67																												M4-11	19	
	2 HR PARKING 8:00 AM TO 8:00 PM	1	12"	18"	1.50																												R7-108	19	
STA 104+76 RT	DO NOT ENTER	1	30"	30"	6.25						1			14' X		X		X															R5-1		E-143
	ONE WAY	1	36"	12"	3.00																												R6-1R		E-142
												LF	LF	LF ~~85~~ 90	LF	LF 85	LF	LF	LF	LB	LB	LB		LB 247	LB	LB	LB								
TOTALS					SF 34.08	SF	EA. 3	SF				LF ~~85~~ 90			LF 85					LB			EA. 2	LB ~~247~~ 169.1 LBS				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: JOHNSON
PROJECT NO.: BRF 030-2(17)S
DESIGN FILE NAME: 91296SGN.dwg
IPARM FILE NAME:
SURVEYED BY: N/A
SQUAD LEADER: JAW
PLOT DATE:
SURVEY DATE: N/A
DRAWN BY: SMC
SHEET: 38 OF 85