

DETOUR SIGN PLACEMENT:

- 1△ VT-103 SOUTHBOUND
 - [B] "A", PCMS, "BRIDGE CLOSED, VT-103 CHESTER, JUNE XX TO AUGUST XX."
 - [B] "C", "DETOUR SOUTH VT-103"
- VT-11 EASTBOUND
 - [A] "D", "DETOUR SOUTH VT-103"
- VT-11 WESTBOUND
 - [A] "P", "END DETOUR NORTH VT-103"
- 2△ VT-11 EASTBOUND
 - [B] "D", "DETOUR SOUTH VT-103"
 - [B] "E", "DETOUR SOUTH VT-103"
 - [A] "D", "DETOUR SOUTH VT-103"
 - [A] "H", "DETOUR SOUTH VT-103"
- VT-11 WESTBOUND
 - [B] "G", "DETOUR NORTH VT-103"
 - [B] "I", "DETOUR NORTH VT-103"
 - [B] "R", "TRUCK ROUTE, DETOUR NORTH VT-103"
 - [A] "J", "DETOUR NORTH VT-103"
- VT-106 SOUTHBOUND
 - [B] "U", "TRUCK ROUTE, DETOUR SOUTH VT-103"
- VT-106 NORTHBOUND
 - [A] "R", "TRUCK ROUTE, DETOUR NORTH VT-103"
- 3△ EXIT 7 - I-91 SOUTH
 - [B] "A", PCMS, "BRIDGE CLOSED, VT-103 CHESTER, JUNE XX TO AUGUST XX."
 - [B] "B", *, "ROCKINGHAM USE EXIT 6, VT-103 THRU TRAFFIC, USE EXIT 7"
 - [B] "C", *, "DETOUR NORTH VT-103" (BEFORE OFF RAMP)
 - [B] "J", "DETOUR NORTH VT-103" (OFF RAMP)
 - [A] "D", *, "DETOUR SOUTH VT-103"
- VT-11 WESTBOUND
 - [A] "J", "DETOUR NORTH VT-103"
- EXIT 7 - I-91 NORTH
 - [B] "L", PCMS, "VT-103, THRU TRAFFIC, USE EXIT 7"
 - [B] "G", *, "DETOUR NORTH VT-103" (BEFORE RAMP)
 - [B] "C", *, "DETOUR NORTH VT-103" (ON RAMP)
- VT-11 EASTBOUND
 - [B] "D", "DETOUR SOUTH VT-103"
 - [B] "E", "DETOUR SOUTH VT-103"
 - [B] "O", "INTERSTATE WEIGHT LIMITS APPLY"
- VT-103 NORTHBOUND

BETWEEN EXIT 6 AND BRIDGE 8

 - "K", "BRIDGE CLOSED X MILES AHEAD LOCAL TRAFFIC ONLY"
 - "K", "BRIDGE CLOSED X MILES AHEAD LOCAL TRAFFIC ONLY"

X IS LOCATION SPECIFIC, 1 SET EVERY 3 MILES FROM BRIDGE 8

- 4△ EXIT 6 - I-91 NORTH
 - [B] "A", PCMS, "BRIDGE CLOSED, VT-103 CHESTER, JUNE XX TO AUGUST XX."
 - [B] "B", *, "ROCKINGHAM USE EXIT 6, VT-103 THRU TRAFFIC, USE EXIT 7"
 - [A] "J", *, "DETOUR NORTH VT-103"
- VT-103 NORTHBOUND
 - [B] "G", "DETOUR NORTH VT-103"
 - [B] "N", "VT103, THRU TRAFFIC, DETOUR VIA I-91N TO EXIT 7"
 - [B] "O", "INTERSTATE WEIGHT LIMITS APPLY"
 - [A] "M", "BRIDGE CLOSED, VT103 CHESTER, SOUTH OF JCT VT 11, X/XX TO X/XX"
 - [A] "N", "VT103, THRU TRAFFIC, DETOUR VIA I-91N TO EXIT 7"
- VT-103 SOUTHBOUND
 - [B] "I", "DETOUR NORTH VT-103"
 - [B] "O", "INTERSTATE WEIGHT LIMITS APPLY"
- I-91 SOUTH
 - [B] "N", *, "VT103, THRU TRAFFIC, DETOUR VIA I-91N TO EXIT 7"
 - [A] "S", *, "END DETOUR SOUTH VT-103"
- 5△ VT-11 EASTBOUND
 - [B] "M", "BRIDGE CLOSED, VT103 CHESTER, SOUTH OF JCT VT 11, X/XX TO X/XX"
 - [B] "T", "TRUCK ROUTE, DETOUR SOUTH VT-103"
 - [B] "D", "DETOUR SOUTH VT-103"
- 6△ VT-103 SOUTHBOUND
 - [B] "M", "BRIDGE CLOSED, VT103 CHESTER, SOUTH OF JCT VT 11, X/XX TO X/XX"
 - [B] "T", "TRUCK ROUTE, DETOUR SOUTH VT-103"
 - [B] "D", "DETOUR SOUTH VT-103"
- VT-103 NORTHBOUND
 - [B] "V", "TRUCK ROUTE, DETOUR SOUTH VT-103"
- VT-10 EASTBOUND
 - [A] "U", "TRUCK ROUTE, DETOUR SOUTH VT-103"
- VT-10 WESTBOUND
 - [B] "P", "END DETOUR NORTH VT-103"
- 7△ VT-106 SOUTHBOUND
 - [B] "M", "BRIDGE CLOSED, VT103 CHESTER, SOUTH OF JCT VT 11, X/XX TO X/XX"
 - [B] "C", "DETOUR SOUTH VT-103"
 - [A] "U", "TRUCK ROUTE, DETOUR SOUTH VT-103"
- VT-106 NORTHBOUND
 - [B] "R", "TRUCK ROUTE, DETOUR NORTH VT-103"
- VT-10 EASTBOUND
 - [B] "U", "TRUCK ROUTE, DETOUR SOUTH VT-103"
- VT-10 WESTBOUND
 - [A] "R", "TRUCK ROUTE, DETOUR NORTH VT-103"

LEGEND

- [A] - PLACE SIGN AFTER INTERSECTION
- [B] - PLACE SIGN BEFORE INTERSECTION
- * - SIGN SHALL MEET FREEWAY OR SPECIAL SIZE REQUIREMENTS

PROJECT NAME: CHESTER	PLOT DATE: 20-SEP-2010
PROJECT NUMBER: BRF 025-1(37)	DRAWN BY: M.FESSEL
FILE NAME: s84e061/s95b168de+our.dgn	CHECKED BY: R.S.YOUNG
PROJECT LEADER: C.P.WILLIAMS	SHEET 7 OF 124
DESIGNED BY: R.S.YOUNG	
DETOUR NOTES	