

QUANTITY SHEET 3

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
					ROADWAY	TRAINING	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							705			705		LF	PROJECT DEMARCATION FENCE	653.55				
					69.09					69.09		SF	TRAFFIC SIGNS, TYPE A	675.20				
					80					80		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
					28					28		EACH	REMOVING SIGNS	675.50				
					1					1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50				
								128		128		CY	SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, CLASS A LOW CEMENT)	900.608				
					1					1		EACH	SPECIAL PROVISION (GUARDRAIL APPROACH SECTION TO CONCRETE BRIDGE RAILING)(TL-2)	900.620				
					3					3		EACH	SPECIAL PROVISION (GUARDRAIL APPROACH SECTION TO CONCRETE BRIDGE RAILING)(TL-3)	900.620				
								2		2		EACH	SPECIAL PROVISION (PRECAST APPROACH SLAB, SUPER-SLAB)(BRIDGE 9)	900.620				
								249		249		LF	SPECIAL PROVISION (BRIDGE RAILING, GALVANIZED STEEL TUBING/CONCRETE COMBINATION)	900.640				
					1					1		LU	SPECIAL PROVISION (NCENTIVE/DISNCENTIVE) (BRIDGE 9) (N.A.B.I.)	900.650				
								280		280		SF	SPECIAL PROVISION (RETAINING WALL)	900.670				