

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
ROADWAY (BRIDGE 8)	TRAINING (BRIDGE 8)	EROSION CONTROL (BRIDGE 8)	BRIDGE NO. 8	FULL C.E. ITEMS (BRIDGE 8)	ROADWAY (BRIDGE 9)	TRAINING (BRIDGE 9)	EROSION CONTROL (BRIDGE 9)	BRIDGE NO. 9	FULL C.E. ITEMS (BRIDGE 9)	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
													BEGIN OPTION AA					
					84					84		LF	18" CAAP .060 (2-2/3 X 1/2)	601.0215				
					84					84		LF	18" PCCSP .064 (2-2/3 X 1/2)	601.0415				
					84					84		LF	18" CPEP	601.0915				
													END OPTION AA					
					1					1		EACH	PRECAST REINFORCED CONCRETE DROP INLET WITH CAST IRON GRATE	604.18				
					2					2		EACH	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40				
					1					1		EACH	CHANGING ELEVATION OF SEWER MANHOLES	604.42				
		10					10			20		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25				
1					1					2		TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15				
		10					10			20		CY	STONE FILL, TYPE I	613.10				
			140							140		CY	STONE FILL, TYPE III	613.12				
								635		635		CY	STONE FILL, TYPE IV	613.13				
51					105					156		LF	PRECAST REINFORCED CONCRETE CURB, TYPE B	616.26				
35					35					70		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10				
					4					4		SF	DETECTABLE WARNING SURFACE	618.30				
					133					133		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21				
4					4					4		EACH	MANUFACTURED TERMINAL SECTION, TANGENT (TL-2)	621.51				
					4					4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
182					210					392		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
360					530					890		LF	TEMPORARY TRAFFIC BARRIER	621.90				
1										1		EACH	ADJUST ELEVATION OF VALVE BOX	629.20				
90					90					180		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
450					720					1170		HR	FLAGGERS	630.15				
				0.5					0.5	1		LS	FIELD OFFICE, ENGINEERS	631.10				
				0.5					0.5	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
				0.5					0.5	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
				1500					1500	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
	260								260	520		HR	EMPLOYEE TRAINEESHIP	634.10				
0.5					0.5					1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
1										1		LS	TRAFFIC CONTROL	641.10				
0.5					0.5					1		LS	PUBLIC RELATIONS OFFICER	641.12				
4										4		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
500					970					1470		LF	4 INCH WHITE LINE	646.20				
500					890					1390		LF	4 INCH YELLOW LINE	646.21				
					76					76		LF	DURABLE 24 INCH STOP BAR	646.480				
					8					8		EACH	DURABLE LETTER OR SYMBOL	646.490				
					72					72		LF	DURABLE CROSSWALK MARKING	646.500				
500					1570					2070		LF	TEMPORARY 4 INCH WHITE LINE	646.600				
500					1665					2165		LF	TEMPORARY 4 INCH YELLOW LINE	646.610				

PROJECT NAME: CHESTER & CHESTER
 PROJECT NUMBER: BRF 025-1(28) & BRF 025-1(37)
 FILE NAME: M:\86e041\Compositeexcel.dgn PLOT DATE: 09/20/2010
 PROJECT LEADER: C.P.WILLIAMS DRAWN BY: D.D.BEARO
 DESIGNED BY: R.S.YOUNG CHECKED BY: E.R.CHARBONNE
 COMPOSITE QUANTITY SHEET #2 SHEET 4 OF 124