

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
						ROADWAY	TRAINING	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
										0.5	0.5		LS	TESTING EQUIPMENT, CONCRETE	631.16				
										0.5	0.5		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										1500	1500		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
											260		HR	EMPLOYEE TRAINEESHIP	634.10				
						0.5					0.5		LS	MOBILIZATION/DEMOBILIZATION	635.11				
						1					1		LS	TRAFFIC CONTROL	641.10				
						0.5					0.5		LS	PUBLIC RELATIONS OFFICER	641.12				
						4					4		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
						500					500		LF	4 INCH WHITE LINE	646.20				
						500					500		LF	4 INCH YELLOW LINE	646.21				
						500					500		LF	TEMPORARY 4 INCH WHITE LINE	646.600				
						500					500		LF	TEMPORARY 4 INCH YELLOW LINE	646.610				
									210		210		SY	GEOTEXTILE UNDER STONE FILL	649.31				
								30			30		SY	GEOTEXTILE FOR SILT FENCE	649.51				
								50			50		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
								10			10		LB	SEED	651.15				
								20			20		LB	FERTILIZER	651.18				
								1			1		TON	AGRICULTURAL LIMESTONE	651.20				
								1			1		TON	HAY MULCH	651.25				
								10			10		CY	TOPSOIL	651.35				
								65			65		SY	GRUBBING MATERIAL	651.40				
								1			1		LS	EPSC PLAN (BRIDGE 8)	652.10				
								8			8		HR	MONITORING EPSC PLAN	652.20				
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
								65			65		SY	TEMPORARY EROSION MATTING	653.20				
								16			16		CY	VEHICLE TRACKING PAD	653.35				
								220			220		LF	BARRIER FENCE	653.50				
								210			210		LF	PROJECT DEMARCATION FENCE	653.55				
						0.66					0.66		SF	TRAFFIC SIGNS, TYPE A	675.20				
						20					20		LF	FLANGED CHANNEL SIGN POST	675.301				
						8					8		EACH	REMOVING SIGNS	675.50				
									10		10		CY	SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, CLASS A LOW CEMENT)	900.608				
						4					4		EACH	SPECIAL PROVISION (GUARDRAIL APPROACH SECTION TO CONCRETE BRIDGE RAILING)(TL-2)	900.620				
									2		2		EACH	SPECIAL PROVISION (PRECAST APPROACH SLAB, SUPER-SLAB)(BRIDGE 8)	900.620				
									122.5		122.5		LF	SPECIAL PROVISION (BRIDGE RAILING, TEXAS)	900.640				
									253		253		LF	SPECIAL PROVISION (PRESTRESSED CONCRETE, NEXT D BEAMS)(NEXT 28 D)	900.640				
						1					1		LU	SPECIAL PROVISION (INCENTIVE / DISINCENTIVE) (BRIDGE 8) (N.A.B.I.)	900.650				

PROJECT NAME: **CHESTER**
PROJECT NUMBER: **BRF 025-1(28)**
FILE NAME: s94e081excel.dgn PLOT DATE: 09/20/2010
PROJECT LEADER: C.P.WILLIAMS DRAWN BY: D.D.BEARD
DESIGNED BY: R.S.YOUNG CHECKED BY: R.S.YOUNG
QUANTITY SHEET #2 SHEET 13 OF 124