

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
					ROADWAY	TRAINING	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
					105					105		LF	PRECAST REINFORCED CONCRETE CURB, TYPE B	616.26				
					35					35		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10				
					4					4		SF	DETECTABLE WARNING SURFACE	618.30				
					133					133		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21				
					4					4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
					210					210		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
					530					530		LF	TEMPORARY TRAFFIC BARRIER	621.90				
					90					90		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
					720					720		HR	FLAGGERS	630.15				
									0.5	0.5		LS	FIELD OFFICE, ENGINEERS	631.10				
									0.5	0.5		LS	TESTING EQUIPMENT, CONCRETE	631.16				
									0.5	0.5		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
									1500	1500		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
						260				260		HR	EMPLOYEE TRANEESHIP	634.10				
					0.5					0.5		LS	MOBILIZATION/DEMOBILIZATION	635.11				
					0.5					0.5		LS	PUBLIC RELATIONS OFFICER	641.12				
					970					970		LF	4 INCH WHITE LINE	646.20				
					890					890		LF	4 INCH YELLOW LINE	646.21				
					76					76		LF	DURABLE 24 INCH STOP BAR	646.480				
					8					8		EACH	DURABLE LETTER OR SYMBOL	646.490				
					72					72		LF	DURABLE CROSSWALK MARKING	646.500				
					1570					1570		LF	TEMPORARY 4 INCH WHITE LINE	646.600				
					1665					1665		LF	TEMPORARY 4 INCH YELLOW LINE	646.610				
					165					165		SF	PAVEMENT MARKING MASK	646.86				
								675		675		SY	GEOTEXTILE UNDER STONE FILL	649.31				
							120			120		SY	GEOTEXTILE FOR SILT FENCE	649.51				
							380			380		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
							20			20		LB	SEED	651.15				
							80			80		LB	FERTILZER	651.18				
							1			1		TON	AGRICULTURAL LIMESTONE	651.20				
							1			1		TON	HAY MULCH	651.25				
							30			30		CY	TOPSOIL	651.35				
							75			75		SY	GRUBBING MATERIAL	651.40				
							1			1		LS	EPSC PLAN (BRIDGE 9)	652.10				
							15			15		HR	MONITORING EPSC PLAN	652.20				
							1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
							580			580		SY	TEMPORARY EROSION MATTING	653.20				
							16			16		CY	VEHICLE TRACKING PAD	653.35				
							4			4		EACH	INLET PROTECTION DEVICE, TYPE I	653.40				
							60			60		LF	BARRIER FENCE	653.50				

PROJECT NAME: **CHESTER**
PROJECT NUMBER: **BRF 025-1(37)**
FILE NAME: s95b168quantitysheets.dgn PLOT DATE: 09/20/2010
PROJECT LEADER: C.P.WILLIAMS DRAWN BY: D.D.BEARD
DESIGNED BY: R.S.YOUNG CHECKED BY: R.S.YOUNG
QUANTITY SHEET #2 SHEET 61 OF 124