

TEMPORARY 4" REFLECTORIZED YELLOW LINE

MILE	MILE	LT	RT	
1.832	2.13	SOLID	SOLID	3146
2.13	2.29	SOLID	DASH	1056
2.29	2.45	DASH	DASH	211
2.45	2.65	DASH	SOLID	1320
2.65	3.120	SOLID	SOLID	4963
END 1 ST SECTION				
BEGIN 2 ND SECTION				
4.480	4.56	SOLID	SOLID	845
4.56	4.63	SOLID	DASH	396
4.63	4.75	DASH	DASH	158
4.75	4.83	SOLID	DASH	528
4.83	5.03	DASH	SOLID	1320
5.03	5.17	SOLID	SOLID	1478
5.17	5.21	SOLID	DASH	264
5.21	5.53	DASH	DASH	422
5.53	5.638	DASH	SOLID	713
END 2 ND SECTION				
				Sub Tot 16,820

ASSUME 50% LOST ON LEVELING

4" YELLOW EST. - 16,820 x 150% = 25,230 LF.

ALTHOUGH NOT SHOWN ON THIS SHEET, THE ϕ SHALL BE BROKEN AT ALL TOWN HIGHWAY INTERSECTIONS AS SHOWN ON THE PLAN DETAIL SHEET.

TEMPORARY 4" REFLECTORIZED WHITE LINE

1.832	3.120	SOLID	SOLID	13,601
4.480	5.638	SOLID	SOLID	12,228

4" WHITE EST 25,829