



NOTE: ALL NEW SIGNS INSTALLED ON THIS PROJECT SHALL BE STAMPED ON THE BACK WITH VAOT, MONTH AND YEAR OF SIGN FABRICATION AND ROUTE WHERE SIGN IS INSTALLED. THE LETTERS AND NUMBERS SHALL BE 1" AND 1/2 ± THE SIGN MATERIAL THICKNESS. (MAX. - 1/8") ALL MATERIAL SHALL BE AS SPECIFIED UNDER SECTION - 675-675 - TRAFFIC SIGNS

COLORS
 LEGEND - BLACK (NON-REFL)
 BACKGROUND - YELLOW (REFL)
 W4-2

SIGN	DIMENSIONS (INCHES)							
	A	B	C	D	E	F	G	H
STD. & EXPWY.	38	5/8	7/8	4	1	10	8	2-1/4

INSTALL NEW, WA-2, 36" SIGN ON NEW 16' x 3 LBS. TYPE A POST, LT AT MY 0.90 WEST HAVEN

ITEM 675.20 - TRAFFIC SIGN TYPEA - 9.0 SF

ITEM 675.35 TYPEA POST - 48 LBS

REMOVE EXISTING W-4-2 SIGN & POST AT MY 0.77 LT, WEST HAVEN.

ITEM 675.51 - REMOVEING SIGNS - 9.0 SF

NOTES: REMOVAL OF POSTS TO BE SUBSIDIARY TO SIGN REMOVAL.

ALL REMOVED SIGNS WILL BECOME PROPERTY OF THE STATE. COMPONENTS WILL BE STOCKPILED IN AN ACCESSIBLE LOCATION FOR PICK-UP BY DISTRICT FORCES.

IN AREAS WHERE LEDGE ROCK IS ENCOUNTERED, STEEL POSTS WILL BE SET AND GROUTED 12" DEEP IN LEDGE. PAYMENT FOR SETTING POST & SIGN SHALL BE CONSIDERED AS BEING INCLUDED IN UNIT PRICES WITH POST ITEM 675.35.

