

PROJECT LENGTHS AND ITEM QUANTITIES

ITEM DESCRIPTION	LENGTH	WIDTH	OVERLAY DEPTH	OPTION													REMARKS										
ITEM NUMBER	402.10	402.11	404.65	406.25	604.40	608.25	608.30	630.10	630.15	635.10	646.35	646.36													REMARKS		
UNIT	FEET	FT	INCH	S.Y.	CY	TON	CWT	TON	EA	HR	HR	HR	HR	LS	LF												
LOCATION																											
Newfane MM 2.24 - 2.60	1900	26	3/4		211	349	14	229									26' wide with 6' Gravel Shoulders 150 T/M Level Factored to 177 T/M										
MM 2.60 - 3.00	2111	26	3/4				15	254									26' Wide 6' Paved Shoulders 150 T/M Level Factored to 177 T/M										
MM 3.00 - 3.20	1056	26	3/4		59	97	8	127									26' Wide with 3' Gravel Shoulders 150 T/M Level Factored to 177 T/M										
MM 3.20 - 3.50	1584	26	3/4		176	290	12	191									26' Wide with 6' Gravel Shoulders 150 T/M Level Factored to 177 T/M										
MM 3.50 - 3.70	1056	26	3/4		59	97	8	127									26' Wide with 3' Gravel Shoulders 150 T/M Level Factored to 177 T/M										
SUB-TOTAL	7707				505	833	64	1305																			